					ST DEPARTMENT DIVISION C	COF N			6		AMEN	FO IDED REPO	RM 3	
		APPI	ICATION F	OR	PERMIT TO DRIL	L				1. WELL NAME and		<b>R</b> 2-36B1CS		
2. TYPE (	<b>DF WORK</b>	RILL NEW WELL (I	REENTER	R P&	A WELL DEEPE	EN WEL	r()			3. FIELD OR WILDC		_ BUTTES		
4. TYPE C	OF WELL	Gas	Well Co	nalbe	ed Methane Well: NO					5. UNIT or COMMUN		TION AGR BUTTES	EEMENT	NAME
6. NAME	OF OPERATOR	R			AS ONSHORE, L.P.					7. OPERATOR PHON	IE	9-6515		
8. ADDRE	SS OF OPERA	TOR			enver, CO, 80217					9. OPERATOR E-MA		anadarko	com	
	RAL LEASE NI L, INDIAN, OF	JMBER		, -	11. MINERAL OWN	-	-		_	12. SURFACE OWNE	RSHIP			_
`		ML-22650 OWNER (if box 1	2 = 'fee')		FEDERAL () INC	DIAN (	) STATE (	<b>J</b> FEE	<u> </u>	FEDERAL IND  14. SURFACE OWNE	R PHO			ree')
15. ADDF	RESS OF SURF	ACE OWNER (if b	ox 12 = 'fee')							16. SURFACE OWNE	R E-MA	IL (if box	12 = 'fe	ee')
17 INDI	AN ALLOTTEE	OR TRIBE NAME			18. INTEND TO COM	MMING	LE PRODUCT	ION FRO	M	19. SLANT				
	2 = 'INDIAN')				YES (Submit 0		ngling Applicat	ion) NO		VERTICAL DIR	ECTION	AL 📵 I	HORIZON	ITAL 🔵
20. LOC	ATION OF WE	LL		FO	OTAGES	Q.	TR-QTR	SECT	TION	TOWNSHIP	R	ANGE	МЕ	RIDIAN
LOCATIO	ON AT SURFAC	CE	674	1 FN	L 2282 FEL		NWNE	3	6	9.0 S	2	2.0 E		S
Top of U	ppermost Pro	ducing Zone	579	FN	L 1821 FEL		NWNE	3	6	9.0 S	2	2.0 E		S
At Total	Depth		579	FN	L 1821 FEL		NWNE	3	6	9.0 S	2	2.0 E		S
21. COUN	ITY	UINTAH			22. DISTANCE TO N		<b>T LEASE LIN</b> 579	IE (Feet)		23. NUMBER OF ACI		<b>DRILLING</b> 40	UNIT	
					25. DISTANCE TO N (Applied For Drillin	g or Co		AME POO	DL	26. PROPOSED DEP MD:	<b>TH</b> 8845	TVD: 880	0	
27. ELEV	ATION - GROU	JND LEVEL 5015			28. BOND NUMBER		13542			29. SOURCE OF DRI WATER RIGHTS APP	PROVAL		IF APPI	ICABLE
					Hole, Casing,	and C	Cement Inf	ormatio	n					
String	Hole Size	Casing Size	<b>Length</b> 0 - 2370		ight Grade & TI 8.0 J-55 LT		Max Mu			Cement Premium Plus		Sacks 170	Yield 1.15	Weight 15.8
Surf	11	8.625	0 - 2370		5.0 J-35 LI	ac .	0.4	+		Premium Plus		270	1.15	15.8
Prod	7.875	4.5	0 - 8845	1	1.6 I-80 LT	&C	12.	.5	Pren	nium Lite High Strer	ngth	290	3.38	11.0
										50/50 Poz		1180	1.31	14.3
					A	TTAC	HMENTS							
	VERIFY T	HE FOLLOWIN	G ARE ATTA	СН	ED IN ACCORDAN	ICE W	ITH THE U	TAH OIL	AND (	GAS CONSERVATION	ON GE	NERAL R	ULES	
<b>⊮</b> w	ELL PLAT OR I	MAP PREPARED B	Y LICENSED S	SUR	VEYOR OR ENGINEE	R	СОМ	IPLETE DI	RILLING	PLAN				
AF	FIDAVIT OF S	TATUS OF SURFA	CE OWNER AG	RE	EMENT (IF FEE SURF	FACE)	FOR	4 5. IF OF	PERATO	R IS OTHER THAN TH	IE LEAS	E OWNER		
DI DRILLED		URVEY PLAN (IF	DIRECTIONAL	LY (	OR HORIZONTALLY		<b>№</b> торо	OGRAPHI	CAL MAI	P				
<b>NAME</b> G	ina Becker			T	ITLE Regulatory Analy	st II	1		PHON	<b>E</b> 720 929-6086				
SIGNAT	URE			D.	<b>ATE</b> 05/13/2011				EMAIL	gina.becker@anadark	co.com			
	1BER ASSIGN 047516100			A	PPROVAL				Book	00 gjill				
									Perr	nit Manager				

NBU 922-36B Pad Drilling Program
1 of 4

# Kerr-McGee Oil & Gas Onshore, L.P.

# **NBU 922-36B1CS**

Surface: 674 FNL / 2282 FEL NWNE BHL: 579 FNL / 1821 FEL NWNE

Section 36 T9S R22E

Unitah County, Utah Mineral Lease: ML-22650

## **ONSHORE ORDER NO. 1**

# **DRILLING PROGRAM**

# 1. & 2. <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	Resource
Uinta	0 - Surface	
Green River	1271	
Birds Nest	1563	Water
Mahogany	1915	Water
Wasatch	4377	Gas
Mesaverde	6573	Gas
MVU2	7559	Gas
MVL1	8155	Gas
TVD	8800	
TD	8845	

# 3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Drilling Program

# 4. <u>Proposed Casing & Cementing Program:</u>

Please refer to the attached Drilling Program

# 5. <u>Drilling Fluids Program</u>:

Please refer to the attached Drilling Program

# 6. <u>Evaluation Program</u>:

Please refer to the attached Drilling Program

NBU 922-36B Pad Drilling Program 2 of 4

#### 7. Abnormal Conditions:

Maximum anticipated bottom hole pressure calculated at 8800' TVD, approximately equals 5,808 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,684 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

#### **8.** Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

#### 9. <u>Variances:</u>

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- · Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

# Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

NBU 922-36B Pad Drilling Program 3 of 4

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

## Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

# Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

## Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 922-36B Pad Drilling Program 4 of 4

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

## Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


# **Other Information:**

Please refer to the attached Drilling Program.



# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE May 6, 2011 NBU 922-36B1CS WELL NAME TD 8,800' TVD 8,845' MD **FIELD** Natural Buttes **COUNTY** Uintah STATE Utah FINISHED ELEVATION 5015.2 SURFACE LOCATION **NWNE** 674 FNL 2282 FEL Sec 36 T 9S R 22E Latitude: 39.997951 Longitude: -109.386379 NAD 27 BTM HOLE LOCATION NWNE 1821 FEL 579 FNL Sec 36 T 9S R 22E Latitude: 39.998207 -109.384735 NAD 27 Longitude: Wasatch/Mesaverde OBJECTIVE ZONE(S)





# **KERR-McGEE OIL & GAS ONSHORE LP**

## **DRILLING PROGRAM**

CASING PROGRAM	<u>1</u>								DESIGN I	FACTORS	
										LTC	BTC
	SIZE	INT	ERVAL	_	WT.	GR.	CPLG.	BURST	COLLA	PSE	TENSION
CONDUCTOR	14"	(	0-40'								
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,370	28.00	IJ-55	LTC	2.28	1.69	5.99	N/A
								7,780	6,350	279,000	367,000
PRODUCTION	4-1/2"	0	to	8,845	11.60	I-80	LTC/BTC	1.11	1.11	3.36	4.42

**Surface Casing:** 

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### **CEMENT PROGRAM**

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1		+ 0.25 pps flocele				
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
		+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to	surface,	option 2 wil	l be utilized	
Option 2 LEAD	1,870'	65/35 Poz + 6% Gel + 10 pps gilsonite	170	35%	11.00	3.82
		+ 0.25 pps Flocele + 3% salt BWOW				
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
		+ 0.25 pps flocele				
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION LEAD	3,875'	Premium Lite II +0.25 pps	290	20%	11.00	3.38
		celloflake + 5 pps gilsonite + 10% gel				
		+ 0.5% extender				
TAIL	4,970'	50/50 Poz/G + 10% salt + 2% gel	1,180	35%	14.30	1.31
		+ 0.1% R-3				

 $<sup>{}^{\</sup>star}$ Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

#### **FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

## ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.


BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.
Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.


DRILLING ENGINEER:		DATE:	
	Nick Spence / Emile Goodwin		
DRILLING SUPERINTENDENT:		DATE:	
	Kenny Gathings / Lovel Young		

<sup>\*</sup>Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

EXHIBIT A NBU 922-36B1CS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



AA/ELL NIAAAE			SURFA	ACE POSIT	ΓΙΟΝ						В	OTTOM HOLE		
WELL NAME		D83	UD5		NAD27	TITLE	FOOT: CT	6	NAE		CITUE	NAD		FOOT 4 373
NBU	<b>LATITUDE</b> 39°59'52.425	LONGIT		<b>LATITUDI</b> 9°59'52.54		ITUDE '10.727"	FOOTAGE		TUDE 50.200"		<b>GITUDE</b> 3'07.572"	<b>LATITUDE</b> 39°59'50.325"	LONGITUDE	905' FNL
922-36B4BS	39.997896°	109°23°13	I	9.997930°			682' FNL 2264' FEL	39.997		1	3 07.572"  85437°	39.997312°	109°23'05.120" 109.384756°	1828' FEL
NBU	39°59'52.464		.298" 39	9°59'52.58	38" 109°23	10.846	678' FNL	_	54.284"		2'50.453"	39°59'54.408"	109°22'48.002"	485' FNL
922-36A1CS	39.997907°	109.38702	.,	9.997941°	103.50		2273' FEL	39.998		_	80681°	39.998447°	109.380001°	494' FEL
NBU	39°59'52.500	.05 =5 .5		9°59'52.62	1.03 =3	10.965	674' FNL	- 1	53.421"		3'07.496"	39°59'53.545"	109°23'05.044"	579' FNL
922-36B1CS NBU	39.997917° 39°59'52.538	109.38706 109°23'13		9.997951° 9°59'52.66		63/9° '11.084"	2282' FEL 671' FNL	39.998	44.926"		85415° 3'07.973"	39.998207° 39°59'45.050"	109.384735° 109°23'05.521"	1821' FEL 1439' FNL
922-36G1BS	39.997927°	109 23 13		9.997962°			2291' FEL	39.995			85548°	39.995847°	109 23 03.321 109.384867°	1861' FEL
NBU	39°59'52.351			9°59'52.47		10.489"	689' FNL							
922-36B	39.997875°	109.38692	<u>28°</u> 39	9.997910°	109.38	6247°	2245' FEL							
						INATES -	From Surfa							
WELL NAME	NORTH	EAST	WELL	NAME	NORTH	EAS		L NAME	NOR	TH	EAST	WELL NAM	IE NORTH	EAST
NBU 922-36B4BS	-224.8'	436.71	NBU 922-36	A1CS	185.81	1,778	.2 NBU	36B1CS	93.0	6'	460.81	NBU 922-36G1B	-770.1	433.71
		BASIS OF THE NE ¼ S.L.B.&M. GLOBAL OBSERVA	OF SEC WHICH POSITIC	TION 36 H IS TAK DNING S	, T9S, R22 EN FROM ATELLITE	?E,		\	_	\	_			
									-20	os3°				
~ \ \ \ \ \ 6>0								A7=	78.52	,70 000	24'	. — — —		
42.5	<sup>45</sup> / <sub>13</sub> "W <sup>24</sup> 639°							AZ= 178°31 (To	115"E	-4/	! <u>-</u>	Az=84.03	3528°	
``\\292	21 W						7	178,21	Dattor	n Ho	le)	Az=84.03 34°02'07"E -	- 1787.90'	_
٠.,	<b>`</b> 4639°` -	<u>.</u>	10'	7 .				(To	Rom	• •	No.			
				10'							_	To Botton	II FIOIC)	
•			$\Xi \cap S$	$S \sim \sim$	<b>● EXIST</b>	ING V	WELL: N	BU 922	2-36B				/ .	
			Az. to Exist. W.H.=112.19694° 50.0¹ NBU 922-36G1BS Az. to Exist. W.H.=112.13333° 40.0¹ NBU 922-36B1CS Az. to Exist. W.H.=112.13333° 40.0¹ NBU 922-36B1CS	Az. to Exist. W.H.=111.94250° 20.0' <b>NBU 922-36B4BS</b>		\$20°123	\$62°45'. To Botton	1117 238 121/E 4 10 Hole						7 ~
	8th Street - De	& Gas (	Onsho	ore, LI	TO NO DE	520	\$62\\To Botton	1117 238 121/E 4 10 Hole	833.097.74		,09	S C A I	L E	7
1099 18		& Gas (	Onsho	ore, LI	TO NO DE	520	\$62°45'. To Botton	1117 238 121/E 4 10 Hole	833° 97.14'	IME	BERLI	SCAI	L E	35) 789-1365
1099 18 WEL	8th Street - De	& Gas ( enver, Colo NBU 92	Onshorado 802 22-36	ore, LI	TO NO DE	520	\$62\\To Botton	1117 238 121/E 4 10 Hole	833° 97.14'	IME ENGII	BERLI	S C A I	L E (42 SURVEYING	35) 789-1365 i, INC.
WELL	Bth Street - Do L PAD - PAD INTI	& Gas ( enver, Colo NBU 9: ERFEREN	Onshorado 802 22-36	ore, LI 202 6B		CLOOLS TOWN HOLE	S62/To Botton	117,236 121/E 4.	833° 97.14'	IME ENGII 209	BERLI NEERIN NORTH 3	S C A I	L E (43 SURVEYING NAL, UTAH 840	35) 789-1365 i, INC. 178
1099 18  WELL  WELL	Bth Street - Do L PAD - PAD INTI BU 922-36B	& Gas ( enver, Colo NBU 92 ERFEREN 4485, NBU	Onshorado 802 22-36 NCE PI	Dre, LI 202 BB LAT B6A1CS,		CONSI	S62, 45%.  To Botton.  609  ULTING, L	117, 236 121/E 4 10 Hole)	833° 97.74′ TI	IME ENGII 209 E SURV	BERLI NEERIN NORTH 3	S C A I	L E (42 SURVEYING RNAL, UTAH 840	35) 789-1365 i, INC.
WELL   WELL   WELLS - NE NBU 92	Bth Street - Do L PAD - PAD INTI BU 922-36B 22-36B1CS	& Gas ( enver, Colo NBU 9: ERFEREN 4485, NBU 8 NBU 9:	Onshorado 802 22-36 NCE PI J 922-3	Dre, LI 202 5B LAT 86A1CS,		CONSI 2155 No.	S62° 45'.  To Botton  609  ULTING, L  orth Main St	117.236 121/E 4. 1 Hole)	833° 97.74′ TI E DATTI 09-02	IME ENGII 209 E SURV	BERLI NEERIN NORTH 3 EYED:	S C A I  INE G & LAND 600 WEST - VER  SURVEYED B	L E (43 SURVEYING RNAL, UTAH 840 8Y: M.S.B.	35) 789-1365 5, INC. 178 SHEET NO:
WELL   WELL   WELLS - NE NBU 92 LOCAT	Bth Street - Do L PAD - PAD INTI BU 922-36B	& Gas ( enver, Colo NBU 9: ERFEREN 4BS, NBU 8 NBU 9: FION 36,	Onshorado 802 22-36 NCE PI J 922-3 22-36G T9S, R2	Dre, LI 202 5B LAT 86A1CS, 11BS 22E,		CONSI 2155 No. Sherida	S62, 45%.  To Botton.  609  ULTING, L	117.236 421/F. 4 10 Hole)	833° 97.74′ TI E DATTI 09-02	ENGII 209 E SURV 2-10 E DRAW	BERLI NEERIN NORTH 3 EYED:	S C A I	L E  (42 SURVEYING RNAL, UTAH 840 BY: M.S.B. E.M.S.	35) 789-1365 i, INC. 178

**EXISTING GRADE @ CENTER OF WELL PAD = 5015.2**1 FINISHED GRADE ELEVATION = 5014.81 **CUT SLOPES = 1:1** FILL SLOPES = 1.5:1**TOTAL WELL PAD AREA = 3.34 ACRES TOTAL DAMAGE AREA = 5.99 ACRES SHRINKAGE FACTOR = 1.10 SWELL FACTOR = 1.00** 

# Kerr-McGee Oil & Gas Onshore, LP

1099 18th Street - Denver, Colorado 80202

**WELL PAD - NBU 922-36B** 

**WELL PAD - LOCATION LAYOUT** NBU 922-36B4BS, NBU 922-36A1CS, NBU 922-36B1CS & NBU 922-36G1BS LOCATED IN SECTION 36, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH



CONSULTING, LLC

2155 North Main Street

Sheridan, WY 82801

Phone 307-674-0609 Fax 307-674-0182

# **WELL PAD QUANTITIES**

TOTAL CUT FOR WELL PAD = 11,616 C.Y. TOTAL FILL FOR WELL PAD = 4,227 C.Y. **TOPSOIL** @ 6" **DEPTH** = 1,575 **C.Y.** EXCESS MATERIAL = 7,389 C.Y.

# **RESERVE PIT QUANTITIES**

**TOTAL CUT FOR RESERVE PIT** +/- 9,740 C.Y. RESERVE PIT CAPACITY (2' OF FREEBOARD) +/- 37,290 BARRELS

# **TIMBERLINE**

**SCALE:** 209 NORTH 300 WEST - VERNAL, UTAH 84078

— PPL — PROPOSED PIPELINE

— EPL — EXISTING PIPELINE

PROPOSED WELL LOCATION

PROPOSED BOTTOM HOLE LOCATION

EXISTING CONTOURS (2' INTERVAL)

PROPOSED CONTOURS (21 INTERVAL)

 $60^{\circ}$ HORIZONTAL E 1" = 60"


2' CONTOURS

SHEET NO: b

6 OF 16

(435) 789-1365 ENGINEERING & LAND SURVEYING, INC.

1"=60' DATE: 12/3/10 JID 4/13/11 **REVISED:** 



K:\ANADARKO\2010 48 NBU FOCUS SEC 36-922\DWGS\NBU 922-36B\NBU 922-36B PAD 20101102.dw

K:\ANADARKO\2010\_48\_NBU\_FOCUS\_SEC\_36-922\DWGS\NBU 922-36B\NBU\_922-36B\_PAD\_20101102.dwg, 1/




PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE






PHOTO VIEW: FROM EXISTING ACCESS ROAD

**CAMERA ANGLE: SOUTHWESTERLY** 

# Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

# **WELL PAD - NBU 922-36B**

**LOCATION PHOTOS** NBU 922-36B4BS, NBU 922-36A1CS, NBU 922-36B1CS & NBU 922-36G1BS LOCATED IN SECTION 36, T9S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH.



# CONSULTING, LLC 2155 North Main Street


Sheridan WY 82801 Phone 307-674-0609 Fax 307-674-0182


TI	M	R	F	R	ı	IN	F


(435) 789-1365


ENGINEERING & LAND SURVEYING, INC. 09 NORTH 300 WEST - VERNAL, UTAH 84078


ı	209 NORTH 300	WEST - VERNAL, UTAIL 64	010
	DATE PHOTOS TAKEN: 09-02-10	PHOTOS TAKEN BY: M.S.B.	SHEET NO:
	DATE DRAWN: 11-16-10	DRAWN BY: E.M.S.	9
	Date Last Revised:		9 OF 16














# Kerr-McGee Oil & Gas Onshore, LP WELL PAD – NBU 922-36B WELLS – NBU 922-36B4BS, NBU 922-36A1CS, NBU 922-36B1CS & NBU 922-36G1BS Section 36, T9S, R22E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 14.4 miles to the intersection of the Fidlar Road (County B Road 3410) which road intersection is approximately 400 feet northeast of the Mountain Fuel Bridge at the White River. Exit left and proceed in a southeasterly direction along the Fidlar Road approximately 4.4 miles to the intersection of the Seven Sisters Road (County B Road 3420). Exit right and proceed in a southerly, then southeasterly direction along the Seven Sisters Road approximately 1.2 miles to a Class D County Road to the southwest. Exit right and proceed in a southwesterly, then southerly direction along the Class D County Road approximately 0.8 miles to an access road approximately 0.1 miles to the proposed well pad.

Total distance from Vernal, Utah to the proposed well location is approximately 44.4 miles in a southerly direction.

API Well Number: 430475161000@oject: Uintah County, UT UTM12 Scientific Drilling

Rocky Mountain Operations


Site: NBU 922-36B PAD


Well: NBU 922-36B1CS


Wellbore: OH

Design: PLAN #1 2-10-11 RHS











# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36B PAD NBU 922-36B1CS

ОН

Plan: PLAN #1 2-10-11 RHS

# **Standard Planning Report**

10 February, 2011





# SDI Planning Report

MD Reference:

North Reference:



EDM5000-RobertS-Local Database:

Company: Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12 Project:

NBU 922-36B PAD Site: Well: NBU 922-36B1CS

Wellbore: ОН

Design: PLAN #1 2-10-11 RHS Local Co-ordinate Reference:

**Survey Calculation Method:** 

TVD Reference:

GL 5015' & KB 4' @ 5019.00ft (ASSUMED)

GL 5015' & KB 4' @ 5019.00ft (ASSUMED)

78.55

Well NBU 922-36B1CS

Minimum Curvature

Project Uintah County, UT UTM12

Map System: Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US Geo Datum: Zone 12N (114 W to 108 W) Map Zone:

System Datum: Mean Sea Level

0.00

0.00

NBU 922-36B PAD, SECTION 36 T9S R22E Site

Northing: 14,529,382.00 usft Site Position: Latitude: 39° 59' 52.548 N From: Lat/Long Easting: 2,092,367.27 usft Longitude: 109° 23' 10.727 W

**Position Uncertainty:** 0.00 ft Slot Radius: 13.200 in **Grid Convergence:** 1.04°

Well NBU 922-36B1CS, 674 FNL 2282 FEL

**Well Position** +N/-S 7.65 ft 14,529,389.31 usft 39° 59' 52.624 N Northing: Latitude:

+E/-W -18.49 ft Easting: 2,092,348.64 usft Longitude: 109° 23' 10.964 W

**Position Uncertainty** 0.00 ft Wellhead Elevation: **Ground Level:** 5.015.00 ft

Wellbore ОН Declination Field Strength Magnetics **Model Name** Sample Date Dip Angle (°) (°) (nT) IGRF2010 02/10/2011 11.07 65.90 52,377

PLAN #1 2-10-11 RHS Design **Audit Notes:** PLAN 0.00 Version: Phase: Tie On Depth: Vertical Section: Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°)

0.00

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
900.00	12.00	78.55	895.62	12.42	61.36	2.00	2.00	0.00	78.55	
2,514.79	12.00	78.55	2,475.12	79.05	390.41	0.00	0.00	0.00	0.00	
3,200.50	0.00	0.00	3,155.84	93.24	460.54	1.75	-1.75	0.00	180.00	
8,844.67	0.00	0.00	8,800.00	93.24	460.54	0.00	0.00	0.00	0.00 PE	3HL_NBU 922-36B



# **SDI**Planning Report



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36B PAD

 Well:
 NBU 922-36B1CS

Wellbore: OH

Design: PLAN #1 2-10-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36B1CS

GL 5015' & KB 4'

@ 5019.00ft (ASSUMED)

GL 5015' & KB 4' @ 5019.00ft (ASSUMED)

True

nned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00		0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00 300.00		0.00 0.00	200.00 300.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00
Start Build		0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00		78.55	399.98	0.35	1.71	1.75	2.00	2.00	0.00
500.00		78.55	499.84	1.38	6.84	6.98	2.00	2.00	0.00
600.00 700.00		78.55 78.55	599.45 698.70	3.11 5.53	15.38 27.33	15.69 27.88	2.00 2.00	2.00 2.00	0.00 0.00
800.00		78.55	797.47	8.64	42.66	43.52	2.00	2.00	0.00
900.00		78.55	895.62	12.42	61.36	62.60	2.00	2.00	0.00
	79 hold at 900.00								
			000.44	40.55	04.74	00.00	0.00	0.00	0.00
1,000.00 1,100.00		78.55 78.55	993.44 1,091.25	16.55 20.67	81.74 102.11	83.39 104.18	0.00 0.00	0.00 0.00	0.00 0.00
1,100.00		78.55	1,189.07	24.80	102.11	104.16	0.00	0.00	0.00
1,283.76		78.55	1,271.00	28.26	139.56	142.39	0.00	0.00	0.00
GREEN RI			.,						
1,300.00		78.55	1,286.88	28.93	142.87	145.77	0.00	0.00	0.00
1,400.00	12.00	78.55	1,384.70	33.05	163.25	166.56	0.00	0.00	0.00
1,500.00		78.55 78.55	1,482.51	37.18	183.62	187.35	0.00	0.00	0.00
1,600.00		78.55	1,580.33	41.30	204.00	208.14	0.00	0.00	0.00
1,700.00		78.55	1,678.14	45.43	224.38	228.93	0.00	0.00	0.00
1,800.00	12.00	78.55	1,775.96	49.56	244.76	249.72	0.00	0.00	0.00
1,900.00	12.00	78.55	1,873.77	53.68	265.13	270.51	0.00	0.00	0.00
2,000.00		78.55	1,971.59	57.81	285.51	291.31	0.00	0.00	0.00
2,100.00	12.00	78.55	2,069.40	61.93	305.89	312.10	0.00	0.00	0.00
2,200.00		78.55	2,167.22	66.06	326.27	332.89	0.00	0.00	0.00
2,300.00	12.00	78.55	2,265.03	70.18	346.65	353.68	0.00	0.00	0.00
2,400.00		78.55	2,362.84	74.31	367.02	374.47	0.00	0.00	0.00
2,402.20	12.00	78.55	2,365.00	74.40	367.47	374.93	0.00	0.00	0.00
8 5/8"									
2,500.00 2,514.79		78.55 78.55	2,460.66 2,475.12	78.44 79.05	387.40 390.41	395.26 398.34	0.00 0.00	0.00 0.00	0.00 0.00
Start Drop		76.55	2,475.12	79.05	390.41	390.34	0.00	0.00	0.00
2,600.00		78.55	2,558.70	82.35	406.71	414.97	1.75	-1.75	0.00
2,700.00		78.55	2,657.28	85.67	423.11	431.70	1.75	-1.75 1.75	0.00
2,800.00 2,900.00		78.55 78.55	2,756.33 2,855.76	88.39 90.51	436.56 447.03	445.42 456.10	1.75 1.75	-1.75 -1.75	0.00 0.00
3,000.00		78.55	2,955.46	92.03	454.52	463.74	1.75	-1.75	0.00
3,100.00		78.55	3,055.35	92.94	459.02	468.34	1.75	-1.75	0.00
3,200.00	0.01	78.55	3,155.33	93.24	460.54	469.88	1.75	-1.75	0.00
3,200.50		0.00	3,155.84	93.24	460.54	469.88	1.75	-1.75	0.00
	16 hold at 3200.50		-,	30.2 .	.00.01	. 30.00	0	0	0.00
3,300.00		0.00	3,255.33	93.24	460.54	469.88	0.00	0.00	0.00
3,400.00		0.00	3,355.33	93.24	460.54	469.88	0.00	0.00	0.00
3,500.00	0.00	0.00	3,455.33	93.24	460.54	469.88	0.00	0.00	0.00
3,600.00	0.00	0.00	3,555.33	93.24	460.54	469.88	0.00	0.00	0.00
3,700.00		0.00	3,655.33	93.24	460.54	469.88	0.00	0.00	0.00
3,800.00		0.00	3,755.33	93.24	460.54	469.88	0.00	0.00	0.00
3,900.00		0.00	3,855.33	93.24	460.54	469.88	0.00	0.00	0.00
4,000.00	0.00	0.00	3,955.33	93.24	460.54	469.88	0.00	0.00	0.00



# **SDI**Planning Report



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36B PAD

 Well:
 NBU 922-36B1CS

Wellbore: OH

Design: PLAN #1 2-10-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36B1CS

GL 5015' & KB 4'

@ 5019.00ft (ASSUMED)

GL 5015' & KB 4' @ 5019.00ft (ASSUMED)

True

sign:	PLAN #1 2-10	-II KU2							
anned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,100.00	0.00	0.00	4,055.33	93.24	460.54	469.88	0.00	0.00	0.00
4,200.00 4,300.00	0.00 0.00	0.00 0.00	4,155.33 4,255.33	93.24 93.24	460.54 460.54	469.88 469.88	0.00 0.00	0.00 0.00	0.00 0.00
4,400.00	0.00	0.00	4,355.33	93.24	460.54	469.88	0.00	0.00	0.00
4,421.67	0.00	0.00	4,377.00	93.24	460.54	469.88	0.00	0.00	0.00
WASATCH									
4,500.00	0.00	0.00	4,455.33	93.24	460.54	469.88	0.00	0.00	0.00
4,600.00	0.00	0.00	4,555.33	93.24	460.54	469.88	0.00	0.00	0.00
4,700.00	0.00	0.00	4,655.33	93.24	460.54	469.88	0.00	0.00	0.00
4,800.00	0.00	0.00	4,755.33	93.24	460.54	469.88	0.00	0.00	0.00
4,900.00	0.00	0.00	4,855.33	93.24	460.54	469.88	0.00	0.00	0.00
5,000.00	0.00	0.00	4,955.33	93.24	460.54	469.88	0.00	0.00	0.00
5,100.00	0.00	0.00	5,055.33	93.24	460.54	469.88	0.00	0.00	0.00
5,200.00	0.00	0.00	5,155.33	93.24	460.54 460.54	469.88	0.00	0.00	0.00
5,300.00 5,400.00	0.00 0.00	0.00 0.00	5,255.33 5,355.33	93.24 93.24	460.54 460.54	469.88 469.88	0.00 0.00	0.00 0.00	0.00 0.00
5,500.00	0.00	0.00	5,455.33	93.24	460.54	469.88	0.00	0.00	0.00
5,600.00 5,700.00	0.00 0.00	0.00 0.00	5,555.33 5,655.33	93.24 93.24	460.54 460.54	469.88 469.88	0.00 0.00	0.00 0.00	0.00 0.00
5,800.00	0.00	0.00	5,755.33	93.24	460.54	469.88	0.00	0.00	0.00
5,900.00	0.00	0.00	5,855.33	93.24	460.54	469.88	0.00	0.00	0.00
6,000.00	0.00	0.00	5,955.33	93.24	460.54	469.88	0.00	0.00	0.00
6,100.00	0.00	0.00	6,055.33	93.24	460.54	469.88	0.00	0.00	0.00
6,200.00	0.00	0.00	6,155.33	93.24	460.54	469.88	0.00	0.00	0.00
6,300.00	0.00	0.00	6,255.33	93.24	460.54	469.88	0.00	0.00	0.00
6,400.00	0.00	0.00	6,355.33	93.24	460.54	469.88	0.00	0.00	0.00
6,500.00	0.00	0.00	6,455.33	93.24	460.54	469.88	0.00	0.00	0.00
6,600.00	0.00	0.00	6,555.33	93.24	460.54	469.88	0.00	0.00	0.00
6,617.67	0.00	0.00	6,573.00	93.24	460.54	469.88	0.00	0.00	0.00
MESAVERD									
6,700.00 6,800.00	0.00 0.00	0.00 0.00	6,655.33 6,755.33	93.24 93.24	460.54 460.54	469.88 469.88	0.00 0.00	0.00 0.00	0.00 0.00
6,900.00 7,000.00	0.00 0.00	0.00 0.00	6,855.33 6,955.33	93.24 93.24	460.54 460.54	469.88 469.88	0.00 0.00	0.00 0.00	0.00 0.00
7,100.00	0.00	0.00	7,055.33	93.24	460.54	469.88	0.00	0.00	0.00
7,200.00	0.00	0.00	7,155.33	93.24	460.54	469.88	0.00	0.00	0.00
7,300.00	0.00	0.00	7,255.33	93.24	460.54	469.88	0.00	0.00	0.00
7,400.00	0.00	0.00	7,355.33	93.24	460.54	469.88	0.00	0.00	0.00
7,500.00	0.00	0.00	7,455.33	93.24	460.54	469.88	0.00	0.00	0.00
7,600.00	0.00	0.00	7,555.33	93.24	460.54	469.88	0.00	0.00	0.00
7,700.00	0.00	0.00	7,655.33	93.24	460.54	469.88	0.00	0.00	0.00
7,800.00	0.00	0.00	7,755.33	93.24	460.54	469.88	0.00	0.00	0.00
7,900.00	0.00	0.00	7,855.33	93.24	460.54	469.88	0.00	0.00	0.00
8,000.00	0.00	0.00	7,955.33	93.24	460.54	469.88	0.00	0.00	0.00
8,100.00 8,200.00	0.00 0.00	0.00 0.00	8,055.33 8,155.33	93.24 93.24	460.54 460.54	469.88 469.88	0.00 0.00	0.00 0.00	0.00 0.00
8,300.00	0.00	0.00	8,255.33	93.24	460.54	469.88	0.00	0.00	0.00
8,400.00	0.00		8.355.33	93.24	460.54	469.88			0.00
8,500.00	0.00	0.00 0.00	8,355.33 8,455.33	93.24 93.24	460.54 460.54	469.88 469.88	0.00 0.00	0.00 0.00	0.00
8,600.00	0.00	0.00	8,555.33	93.24	460.54	469.88	0.00	0.00	0.00
8,700.00	0.00	0.00	8,655.33	93.24	460.54	469.88	0.00	0.00	0.00
8,800.00	0.00	0.00	8,755.33	93.24	460.54	469.88	0.00	0.00	0.00



# **SDI**Planning Report



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

.....

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36B PAD

 Well:
 NBU 922-36B1CS

Wellbore: OH

Design: PLAN #1 2-10-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

Survey Calculation Method:

Well NBU 922-36B1CS

GL 5015' & KB 4'

@ 5019.00ft (ASSUMED)

GL 5015' & KB 4'

@ 5019.00ft (ASSUMED)

True

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,844.67	0.00	0.00	8,800.00	93.24	460.54	469.88	0.00	0.00	0.00
PBHL_NBU	922-36B1CS								

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 922-36B1Cl - plan hits target cen - Circle (radius 25.00	ter	0.00	8,800.00	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W

Casing Points					
	Measured	Vertical		Casing	Hole
	Depth	Depth		Diameter	Diameter
	(ft)	(ft)	Name	(in)	(in)
	2,402.20	2,365.00 8 5/8		8.625	11.000

Formations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,283.76 4,421.67 6,617.67	4,377.00	GREEN RIVER WASATCH MESAVERDE				

Plan Annotations				
Measure Depth (ft)	d Vertical Depth (ft)	Local Coord +N/-S (ft)	dinates +E/-W (ft)	Comment
300	00 300.00	0.00	0.00	Start Build 2.00
900	00 895.62	12.42	61.36	Start 1614.79 hold at 900.00 MD
2,514	79 2,475.12	79.05	390.41	Start Drop -1.75
3,200	50 3,155.84	93.24	460.54	Start 5644.16 hold at 3200.50 MD
8,844	67 8,800.00	93.24	460.54	TD at 8844.67



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36B PAD NBU 922-36B1CS

OH

Plan: PLAN #1 2-10-11 RHS

# **Standard Planning Report - Geographic**

10 February, 2011





# **SDI**Planning Report - Geographic



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

.....

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36B PAD

 Well:
 NBU 922-36B1CS

Wellbore: OH

Design: PLAN #1 2-10-11 RHS

Local Co-ordinate Reference:

**Survey Calculation Method:** 

TVD Reference:

MD Reference:

North Reference:

GL 5015' & KB 4' @ 5019.00ft (ASSUMED)

GL 5015' & KB 4'

Well NBU 922-36B1CS

@ 5019.00ft (ASSUMED)

True

Minimum Curvature

Project Uintah County, UT UTM12

Map System: Universal Transverse Mercator (US Survey Feet)

 Geo Datum:
 NAD 1927 - Western US

 Map Zone:
 Zone 12N (114 W to 108 W)

System Datum: Mean Sea Level

Site NBU 922-36B PAD, SECTION 36 T9S R22E Northing: 14,529,382.00 usft Site Position: Latitude: 39° 59' 52.548 N 109° 23' 10.727 W 2,092,367.27 usft Lat/Long Easting: From: Longitude: Slot Radius: 0.00 ft 13.200 in 1.04 9 **Position Uncertainty: Grid Convergence:** 

NBU 922-36B1CS, 674 FNL 2282 FEL Well 39° 59' 52.624 N **Well Position** +N/-S 0.00 ft Northing: 14,529,389.31 usft Latitude: +E/-W 0.00 ft 2,092,348.64 usft Longitude: 109° 23' 10.964 W Easting: 0.00 ft 5,015.00 ft **Position Uncertainty** Wellhead Elevation: **Ground Level:** 

 Wellbore
 OH

 Magnetics
 Model Name
 Sample Date (°)
 Declination (°)
 Dip Angle (°)
 Field Strength (nT)

 IGRF2010
 02/10/2011
 11.07
 65.90
 52,377

PLAN #1 2-10-11 RHS Design **Audit Notes:** PLAN 0.00 Version: Phase: Tie On Depth: +N/-S Vertical Section: Depth From (TVD) +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 78.55

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
900.00	12.00	78.55	895.62	12.42	61.36	2.00	2.00	0.00	78.55	
2,514.79	12.00	78.55	2,475.12	79.05	390.41	0.00	0.00	0.00	0.00	
3,200.50	0.00	0.00	3,155.84	93.24	460.54	1.75	-1.75	0.00	180.00	
8,844.67	0.00	0.00	8,800.00	93.24	460.54	0.00	0.00	0.00	0.00 P	BHL_NBU 922-36B



# SDI Planning Report - Geographic



EDM5000-RobertS-Local Database:

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

Site: NBU 922-36B PAD Well: NBU 922-36B1CS

Wellbore:

Design: PLAN #1 2-10-11 RHS Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36B1CS

GL 5015' & KB 4'

@ 5019.00ft (ASSUMED) GL 5015' & KB 4'

@ 5019.00ft (ASSUMED) True

Planned Survey	,								
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,529,389.31	2,092,348.64	39° 59' 52.624 N	109° 23' 10.964 W
100.00	0.00	0.00	100.00	0.00	0.00	14,529,389.31	2,092,348.64	39° 59' 52.624 N	109° 23' 10.964 W
200.00		0.00	200.00	0.00	0.00	14,529,389.31	2,092,348.64	39° 59' 52.624 N	109° 23' 10.964 W
300.00	0.00	0.00	300.00	0.00	0.00	14,529,389.31	2,092,348.64	39° 59' 52.624 N	109° 23' 10.964 W
Start Bu		70 55	399.98	0.25	1.71	14 520 290 60	2 002 250 25	20° 50' 52 627 N	109° 23' 10.942 W
400.00 500.00	2.00 4.00	78.55 78.55	399.96 499.84	0.35 1.38	6.84	14,529,389.69 14,529,390.82	2,092,350.35 2,092,355.46	39° 59' 52.627 N 39° 59' 52.637 N	109° 23' 10.877 W
600.00	6.00	78.55	599.45	3.11	15.38	14,529,392.70	2,092,363.96	39° 59' 52.654 N	109° 23' 10.767 W
700.00	8.00	78.55	698.70	5.53	27.33	14,529,395.34	2,092,375.86	39° 59' 52.678 N	109° 23' 10.613 W
800.00	10.00	78.55	797.47	8.64	42.66	14,529,398.72	2,092,391.14	39° 59' 52.709 N	109° 23' 10.416 W
900.00	12.00	78.55	895.62	12.42	61.36	14,529,402.84	2,092,409.76	39° 59' 52.746 N	109° 23' 10.176 W
Start 161	14.79 hold at 9	00.00 MD							
1,000.00	12.00	78.55	993.44	16.55	81.74	14,529,407.34	2,092,430.06	39° 59' 52.787 N	109° 23' 9.914 W
1,100.00	12.00	78.55	1,091.25	20.67	102.11	14,529,411.83	2,092,450.36	39° 59' 52.828 N	109° 23' 9.652 W
1,200.00	12.00	78.55	1,189.07	24.80	122.49	14,529,416.32	2,092,470.66	39° 59' 52.869 N	109° 23' 9.390 W
1,283.76		78.55	1,271.00	28.26	139.56	14,529,420.09	2,092,487.67	39° 59' 52.903 N	109° 23' 9.171 W
GREEN									
1,300.00	12.00	78.55	1,286.88	28.93	142.87	14,529,420.82	2,092,490.96	39° 59' 52.910 N	109° 23' 9.128 W
1,400.00	12.00	78.55	1,384.70	33.05	163.25	14,529,425.31	2,092,511.26	39° 59' 52.950 N	109° 23' 8.867 W
1,500.00	12.00 12.00	78.55 78.55	1,482.51 1,580.33	37.18 41.30	183.62 204.00	14,529,429.81 14,529,434.30	2,092,531.56 2,092,551.86	39° 59' 52.991 N	109° 23' 8.605 W 109° 23' 8.343 W
1,600.00 1,700.00	12.00	78.55	1,678.14	45.43	224.38	14,529,434.30	2,092,572.16	39° 59' 53.032 N 39° 59' 53.073 N	109° 23' 8.081 W
1,800.00	12.00	78.55	1,775.96	49.56	244.76	14,529,443.29	2,092,592.46	39° 59' 53.113 N	109° 23' 7.819 W
1,900.00	12.00	78.55	1,873.77	53.68	265.13	14,529,447.78	2,092,612.76	39° 59' 53.154 N	109° 23' 7.557 W
2,000.00	12.00	78.55	1,971.59	57.81	285.51	14,529,452.28	2,092,633.06	39° 59' 53.195 N	109° 23' 7.295 W
2,100.00	12.00	78.55	2,069.40	61.93	305.89	14,529,456.77	2,092,653.36	39° 59' 53.236 N	109° 23' 7.033 W
2,200.00	12.00	78.55	2,167.22	66.06	326.27	14,529,461.26	2,092,673.66	39° 59' 53.277 N	109° 23' 6.772 W
2,300.00	12.00	78.55	2,265.03	70.18	346.65	14,529,465.76	2,092,693.96	39° 59' 53.317 N	109° 23' 6.510 W
2,400.00	12.00	78.55	2,362.84	74.31	367.02	14,529,470.25	2,092,714.26	39° 59' 53.358 N	109° 23' 6.248 W
2,402.20	12.00	78.55	2,365.00	74.40	367.47	14,529,470.35	2,092,714.71	39° 59' 53.359 N	109° 23' 6.242 W
8 5/8"									
2,500.00	12.00	78.55	2,460.66	78.44	387.40	14,529,474.75	2,092,734.56	39° 59' 53.399 N	109° 23' 5.986 W
2,514.79	12.00	78.55	2,475.12	79.05	390.41	14,529,475.41	2,092,737.56	39° 59' 53.405 N	109° 23' 5.947 W
Start Dro	-	70.55	0.550.70	00.05	400.74	44 500 470 04	0.000.750.00	20° 501 52 427 N	400° 001 F 700 W
2,600.00 2,700.00	10.51 8.76	78.55 78.55	2,558.70 2,657.28	82.35 85.67	406.71 423.11	14,529,479.01 14,529,482.62	2,092,753.80 2,092,770.14	39° 59' 53.437 N 39° 59' 53.470 N	109° 23' 5.738 W 109° 23' 5.527 W
2,800.00	7.01	78.55	2,756.33	88.39	436.56	14,529,485.59	2,092,770.14	39° 59' 53.497 N	109° 23' 5.354 W
2,900.00	5.26	78.55	2,855.76	90.51	447.03	14,529,487.90	2,092,793.96	39° 59' 53.518 N	109° 23' 5.220 W
3,000.00	3.51	78.55	2,955.46	92.03	454.52	14,529,489.55	2,092,801.42	39° 59' 53.533 N	109° 23' 5.123 W
3,100.00	1.76	78.55	3,055.35	92.94	459.02	14,529,490.54	2,092,805.91	39° 59' 53.542 N	109° 23' 5.065 W
3,200.00	0.01	78.55	3,155.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
3,200.50		0.00	3,155.84	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
Start 564	14.16 hold at 3	3200.50 MD							
3,300.00	0.00	0.00	3,255.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
3,400.00		0.00	3,355.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
3,500.00		0.00	3,455.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
3,600.00	0.00	0.00	3,555.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
3,700.00	0.00	0.00	3,655.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
3,800.00	0.00	0.00	3,755.33	93.24	460.54 460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
3,900.00 4,000.00	0.00	0.00 0.00	3,855.33 3,955.33	93.24 93.24	460.54 460.54	14,529,490.88 14,529,490.88	2,092,807.41 2,092,807.41	39° 59' 53.545 N 39° 59' 53.545 N	109° 23' 5.046 W 109° 23' 5.046 W
4,100.00	0.00	0.00	3,955.33 4,055.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
4,100.00	0.00	0.00	₩,000.00	33.24	400.04	14,525,450.00	۷,002,001.41	Ja Ja JJ.J4J IN	109 23 3.040 W



# **SDI**Planning Report - Geographic



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12

 Site:
 NBU 922-36B PAD

 Well:
 NBU 922-36B1CS

Wellbore: OH

Design: PLAN #1 2-10-11 RHS

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Well NBU 922-36B1CS

GL 5015' & KB 4'

@ 5019.00ft (ASSUMED)

GL 5015' & KB 4' @ 5019.00ft (ASSUMED)

True

Measured   Depth   Inclination   Azimuth   Depth   H)/-S   H2/AW   (ft)   (ft) (ft) (gt) (gt) (gsft) (usft)   Latitude   Langitude	Planned Survey									
4,300.00 0,00 0,00 4,255.33 93.24 480.54 14,529.490.88 2,092.807.41 39° 59° 53.545 N 109° 23° 5,046 W 4,271.67 0,00 0,00 4,377.00 93.24 480.54 14,529.490.88 2,092.807.41 39° 59° 53.545 N 109° 23° 5,046 W 4,000.00 0,00 0,00 4,555.33 93.24 480.54 14,529.490.88 2,092.807.41 39° 59° 53.545 N 109° 23° 5,046 W 4,000.00 0,00 0,00 4,555.33 93.24 480.54 14,529.490.88 2,092.807.41 39° 59° 53.545 N 109° 23° 5,046 W 4,000.00 0,00 0,00 4,555.33 93.24 480.54 14,529.490.88 2,092.807.41 39° 59° 53.545 N 109° 23° 5,046 W 4,000.00 0,00 0,00 4,755.33 93.24 480.54 14,529.490.88 2,092.807.41 39° 59° 53.545 N 109° 23° 5,046 W 4,000.00 0,00 0,00 4,755.33 93.24 480.54 14,529.490.88 2,092.807.41 39° 59° 53.545 N 109° 23° 5,046 W 5,000.00 0,00 0,00 4,855.33 93.24 480.54 14,529.490.88 2,092.807.41 39° 59° 53.545 N 109° 23° 5,046 W 5,000.00 0,00 0,00 4,955.33 93.24 480.54 14,529.490.88 2,092.807.41 39° 59° 53.545 N 109° 23° 5,046 W 5,000.00 0,00 0,00 0,00 0,00 0,00 0,00	Depth			Depth			Northing	Easting	Latitude	Longitude
4,400.00 0.00 0.00 4,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  WASATCH  4,500.00 0.00 0.00 4,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  4,700.00 0.00 0.00 4,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  4,700.00 0.00 0.00 4,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  4,800.00 0.00 0.00 0.00 4,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  4,800.00 0.00 0.00 0.00 4,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  4,900.00 0.00 0.00 0.00 4,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  4,900.00 0.00 0.00 0.00 4,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5,046 W  5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88	4,200.00	0.00	0.00	4,155.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
MASATCH   421.67	4,300.00	0.00	0.00	4,255.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
## WASATCH ## 4500.00	4,400.00	0.00	0.00	4,355.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
4,500.00 0.00 0.00 4,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 4,700.00 0.00 0.00 0.00 4,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 4,800.00 0.00 0.00 4,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 4,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 4,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 0.00 0.00 0.00 0.00	4,421.67	0.00	0.00	4,377.00	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
4,600.00 0.00 0.00 4,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 4,900.00 0.00 0.00 4,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 4,900.00 0.00 0.00 4,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 4,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 5,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 5,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 5,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,000.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,500.00 0.00 0.00 0.00 0.00 0.00 0.00	WASATO									
4,700.00 0.00 0.00 4,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 4,900.00 0.00 0.00 4,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,000.00 0.00 0.00 4,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,000.00 0.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,000.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,000.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,000.00 0.00 0.00 5,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,000.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,000.00 0.00 0.00 5,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,500.00 0.00 0.00 5,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 6,000.00 0.00 0.00 5,565.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 6,000.00 0.00 0.00 5,565.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 6,000.00 0.00 0.00 6,565.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 6,000.00 0.00 0.00 6,565.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 6,000.00 0.00 0.00 6,565.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 22′ 5,046 W 6	4,500.00			4,455.33				2,092,807.41	39° 59' 53.545 N	
4,800.00 0.00 0.00 4,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 4,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 5,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 5,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 5,565.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 5,565.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,000.00 0.00 0.00 5,565.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,800.00 0.00 0.00 5,565.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,800.00 0.00 0.00 5,765.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 5,800.00 0.00 0.00 5,765.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 22° 5,046 W 6,000.							, ,			
\$\begin{array}{cccccccccccccccccccccccccccccccccccc				,			, ,			
5,000.00 0.00 0.00 4,955.33 93.24 460.54 14,529,408.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,155.33 93.24 460.54 14,529,408.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,255.33 93.24 460.54 14,529,408.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,355.33 93.24 460.54 14,529,408.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,355.33 93.24 460.54 14,529,408.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 5,000.00 0.00 0.00 5,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,100.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,100.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,100.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,000.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,000.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,000.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,000.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53,545 N 109° 23′ 5,046 W 6,000.										
5,100.00 0.00 0.00 5,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,300.00 0.00 0.00 5,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,400.00 0.00 0.00 5,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,500.00 0.00 0.00 5,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,600.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,600.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,800.00 0.00 0.00 5,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,800.00 0.00 0.00 5,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,800.00 0.00 0.00 5,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 5,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.										
5,200.00 0.00 0.00 5,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,400.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,600.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,600.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,600.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,600.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,600.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,900.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.	· ·									
5,300.00 0.00 0.00 5,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,400.00 0.00 0.00 5,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,600.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,700.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,900.00 0.00 0.00 5,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 5,900.00 0.00 0.00 5,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,000.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,200.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,200.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,300.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,600.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,600.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,600.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,600.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 6,600.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59° 53.545 N 109° 23° 5.046 W 7,000.	· ·									
5,400.00 0.00 0.00 5,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,500.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,700.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,800.00 0.00 0.00 5,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,800.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,100.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,400.00 0.00 0.00 6,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.	· ·									
5,500.00 0.00 0.00 5,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,600.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,800.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,800.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,100.00 0.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,400.00 0.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,400.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545	· ·									
5,600.00 0.00 0.00 5,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,700.00 0.00 0.00 5,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,900.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 5,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,100.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,100.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,100.00 0.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,100.00 0.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109										
5,700.00 0.00 0.00 5,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 5,800.00 0.00 0.00 5,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 5,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,100.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.	· ·						, ,			
5,800.00 0.00 0.00 5,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,000.00 0.00 0.00 5,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,100.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,573.30 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,900.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,900.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.	· ·									
5,900.00 0.00 0.00 5,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,000.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,200.00 0.00 0.00 6,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,300.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,500.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,617.67 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,617.67 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,617.67 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,800.00 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,800.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,800.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.	· ·									
6,000.00 0.00 0.00 5,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,400.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,400.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.	· ·									
6,100.00 0.00 0.00 6,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,200.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,400.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,900.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,200.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.	· ·						, ,			
6,200.00 0.00 0.00 6,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,400.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,900.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,200.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,200.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,200.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.	· ·									
6,300.00 0.00 0.00 6,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,400.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,500.00 0.00 0.00 6,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W MESAVERDE  6,700.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,900.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,200.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,200.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,200.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.0	· ·									
6,400.00 0.00 0.00 6,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,500.00 0.00 0.00 6,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,617.67 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,800.00 0.00 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,800.00 0.00 0.00 0.00 6,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,900.00 0.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,200.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,200.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545	· ·									
6,500.00 0.00 0.00 6,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,617.67 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W MESAVERDE 6,700.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,800.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,900.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,100.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,200.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,200.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,200.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.04	· ·									
6,600.00 0.00 0.00 6,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,617.67 0.00 0.00 6,573.00 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W MESAVERDE 6,700.00 0.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,800.00 0.00 0.00 0.00 6,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 6,900.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,000.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,100.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,200.00 0.00 0.00 7,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,400.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109° 23′ 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59′ 53.545 N 109	· ·									
6,617.67         0.00         0.00         6,573.00         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           MESAVERDE           6,700.00         0.00         0.00         6,655.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           6,800.00         0.00         0.00         6,755.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           6,900.00         0.00         0.00         6,855.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           7,000.00         0.00         0.00         6,955.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           7,100.00         0.00         0.00         7,055.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           7,200.00         0.00         0.00         7,155.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545	· ·									
MESAVERDE           6,700.00         0.00         0.00         6,655.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           6,800.00         0.00         0.00         6,755.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           6,900.00         0.00         0.00         6,855.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           7,000.00         0.00         0.00         6,955.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           7,100.00         0.00         0.00         7,055.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           7,200.00         0.00         0.00         7,055.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545 N         109° 23' 5.046 W           7,200.00         0.00         0.00         7,155.33         93.24         460.54         14,529,490.88         2,092,807.41         39° 59' 53.545	· ·									
6,700.00 0.00 0.00 6,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,800.00 0.00 0.00 6,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,900.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,100.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,200.00 0.00 0.00 7,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,400.00 0.00 0.00 7,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.				-,			,,	, , , , , ,		
6,800.00 0.00 0.00 6,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 6,900.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,100.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,200.00 0.00 0.00 7,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,400.00 0.00 0.00 7,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,700.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,700.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.			0.00	6.655.33	93.24	460.54	14.529.490.88	2.092.807.41	39° 59' 53.545 N	109° 23' 5.046 W
6,900.00 0.00 0.00 6,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,000.00 0.00 0.00 6,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,100.00 0.00 0.00 7,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,200.00 0.00 0.00 7,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,300.00 0.00 0.00 7,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,400.00 0.00 0.00 7,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,500.00 0.00 0.00 7,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,600.00 0.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,700.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,700.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,700.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.04	· ·									
7,000.00       0.00       6,955.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,100.00       0.00       0.00       7,055.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,200.00       0.00       0.00       7,155.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,300.00       0.00       0.00       7,255.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,400.00       0.00       0.00       7,355.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,500.00       0.00       0.00       7,455.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,600.00       0.00       0.00       7,555.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,700.00       0.00       0.00       7,655.33       93.24       460.54       14,529,	· ·									
7,200.00       0.00       0.00       7,155.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,300.00       0.00       0.00       7,255.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,400.00       0.00       0.00       7,355.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,500.00       0.00       0.00       7,455.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,600.00       0.00       0.00       7,555.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,700.00       0.00       0.00       7,655.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,800.00       0.00       0.00       7,655.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,800.00       0.00       0.00       7,755.33       93.24       460.54 <td></td>										
7,300.00       0.00       0.00       7,255.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,400.00       0.00       0.00       7,355.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,500.00       0.00       0.00       7,455.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,600.00       0.00       0.00       7,555.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,700.00       0.00       0.00       7,655.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,800.00       0.00       0.00       7,755.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W	7,100.00	0.00	0.00	7,055.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
7,400.00       0.00       0.00       7,355.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,500.00       0.00       0.00       7,455.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,600.00       0.00       0.00       7,555.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,700.00       0.00       0.00       7,655.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,800.00       0.00       0.00       7,755.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W	7,200.00	0.00	0.00	7,155.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
7,500.00       0.00       0.00       7,455.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,600.00       0.00       0.00       7,555.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,700.00       0.00       0.00       7,655.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W         7,800.00       0.00       0.00       7,755.33       93.24       460.54       14,529,490.88       2,092,807.41       39° 59' 53.545 N       109° 23' 5.046 W	7,300.00	0.00	0.00	7,255.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
7,600.00 0.00 7,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,700.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W	7,400.00	0.00	0.00	7,355.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
7,700.00 0.00 0.00 7,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 7,800.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W	7,500.00	0.00	0.00	7,455.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
7,800.00 0.00 0.00 7,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W	7,600.00	0.00	0.00	7,555.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
	7,700.00	0.00	0.00	7,655.33	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
7,900.00 0.00 0.00 7,855.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W			0.00		93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W
	7,900.00		0.00	7,855.33			14,529,490.88		39° 59' 53.545 N	
8,000.00 0.00 0.00 7,955.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W										
8,100.00 0.00 0.00 8,055.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W										
8,200.00 0.00 0.00 8,155.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W										
8,300.00 0.00 0.00 8,255.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W										
8,400.00 0.00 0.00 8,355.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W										
8,500.00 0.00 0.00 8,455.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W										
8,600.00 0.00 0.00 8,555.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 8,700.00 0.00 0.00 8,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W										
8,700.00 0.00 0.00 8,655.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W 8,800.00 0.00 0.00 8,755.33 93.24 460.54 14,529,490.88 2,092,807.41 39° 59' 53.545 N 109° 23' 5.046 W										



# SDI Planning Report - Geographic



EDM5000-RobertS-Local Database:

Company: Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12 Project:

Site: NBU 922-36B PAD

Well: NBU 922-36B1CS

Wellbore:

Design: PLAN #1 2-10-11 RHS Local Co-ordinate Reference:

**Survey Calculation Method:** 

TVD Reference:

North Reference:

GL 5015' & KB 4' @ 5019.00ft (ASSUMED) MD Reference:

GL 5015' & KB 4' @ 5019.00ft (ASSUMED)

Well NBU 922-36B1CS

True

Planned Survey									
Measured Depth I	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
8,844.67	0.00	0.00	8,800.00	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 922-36B1C: - plan hits target cen - Circle (radius 25.00	ter	0.00	8,800.00	93.24	460.54	14,529,490.88	2,092,807.41	39° 59' 53.545 N	109° 23' 5.046 W

Casing Points						
	Measured Depth	Vertical Depth		Casing Diameter	Hole Diameter	
	(ft)	(ft)	Name	(in)	(in)	
	2,402.20	2,365.00 8 5/8"		8.625	11.000	

Formations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,283.76	1,271.00	GREEN RIVER				
	4,421.67	4,377.00	WASATCH				
	6,617.67	6,573.00	MESAVERDE				

Plan Annotations					
Mea	asured	Vertical	Local Coordinates		
D	epth	Depth	+N/-S	+E/-W	
	(ft)	(ft)	(ft)	(ft)	Comment
	300.00	300.00	0.00	0.00	Start Build 2.00
	900.00	895.62	12.42	61.36	Start 1614.79 hold at 900.00 MD
2	2,514.79	2,475.12	79.05	390.41	Start Drop -1.75
3	3,200.50	3,155.84	93.24	460.54	Start 5644.16 hold at 3200.50 MD
8	3,844.67	8,800.00	93.24	460.54	TD at 8844.67

# **NBU 922-36A1CS**

Surface: 678' FNL 2273' FEL (NW/4NE/4) BHL: 485' FNL 494' FEL (NE/4NE/4)

# **NBU 922-36B1CS**

Surface: 674' FNL 2282' FEL (NW/4NE/4) BHL: 579' FNL 1821' FEL (NW/4NE/4)

## NBU 922-36B4BS

Surface: 682' FNL 2264' FEL (NW/4NE/4) BHL: 905' FNL 1828' FEL (NW/4NE/4)

## **NBU 922-36G1BS**

Surface: 671' FNL 2291' FEL (NW/4NE/4) BHL: 1439' FNL 1861' FEL (SW/4NE/4)

> Pad: NBU 922-36B Pad Section 36 T9S R22E Mineral Lease: ML-22650

Uintah County, Utah Operator: Kerr-McGee Oil & Gas Onshore LP

# MULTI-POINT SURFACE USE PLAN of OPERATIONS (SUPO)

This SUPO contains surface operating procedures for Kerr-McGee Oil & Gas Onshore LP (KMG), a wholly owned subsidiary of Anadarko Petroleum Corporation (APC) pertaining to actions that involve the State of Utah School and Institutional Trust Lands Administration (SITLA) in the development of minerals leased to APC/KMG (including, but not limited to, APDs/SULAs/ROEs/ROWs and/or easements).

See associated Utah Division of Oil, Gas, and Mining (UDOGM) Form 3(s), plats, maps, and other attachments for site-specific information on projects represented herein.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

# A. **Existing Roads**:

Existing roads consist of county roads and improved/unimproved lease roads. KMG will maintain existing roads in a condition that is the same as or better than before operations began and in a safe and usable condition. Maintenance of existing roads will continue until final abandonment and reclamation of well pads and/or other facilities. The road maintenance may include, but is not limited to, blading, ditching, culvert installation/cleanout, surfacing, and dust control.

# NBU 922-36A1CS / 36B1CS/ 36B4BS/ 36G1BS

Surface Use Plan of Operations Page 2

Typically, roads, gathering lines and electrical distribution lines will occupy common disturbance corridors and roadways will be used as working space. All disturbances located in the same corridor will overlap each other to the maximum extent possible; in no case will the maximum disturbance width of the access road and utility corridors exceed 50', unless otherwise approved.

# B. Planned Access Roads:

No new access road is proposed. (see Topo Map B). Applicable Uintah County encroachment and/or pipeline crossing permits will be obtained prior to construction/development. No other pipelines will be crossed at this location.

If there are roads that are new or to be reconstructed, they will be located, designed, and maintained to meet the standards of SITLA and other commonly accepted Best Management Practices (BMPs). If a new road/corridor were to cross a water of the United States, KMG will adhere to the requirements of applicable Nationwide or Individual Permits of the Department of Army Corps of Engineers.

During the onsite, turnouts, major cut and fills, culverts, bridges, gates, cattle guards, low water crossings, or modifications needed to existing infrastructure/facilities were determined, as applicable, are typically shown on attached Exhibits and Topo maps.

# C. Location of Existing and Proposed Facilities:

This pad will expand the existing pad for the NBU 922-36B. The NBU 922-36B well location is a vertical producing well according to Utah Division of Oil, Gas and Mining (UDOGM) records as of May 5, 2011.

Production facilities (see Well Pad Design Summary and Facilities Diagram):

Production facilities will be installed on the disturbed portion of the well pad and may include bermed components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will be constructed of compacted subsoil or corrugated metal, impervious, designed to hold 110% of the capacity of the largest tank, and be independent of the back cut. All permanent (on-site six months or longer) above ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth-tone color chosen at the onsite in coordination with SITLA.

Production tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks are not to be used for disposal of liquids from additional sources without prior approval of UDOGM.

# **Gathering facilities:**

# NBU 922-36A1CS / 36B1CS/ 36B4BS/ 36G1BS

# Surface Use Plan of Operations Page 3

The following pipeline transmission facilities will apply if the well is productive (see Topo D):

The total gas gathering (steel line pipe with fusion bond epoxy coating) pipeline distances from the meter to the tie in point is  $\pm 3,760$ ' and the individual segments are broken up as follows:

- ±40' (0.01 miles) –New 6" buried gas pipeline from the meter to the 36C intersection on pad. Please refer to Topo D2.
- ±450' (0.09 miles) –New 16" buried gas pipeline from the 36C intersection to the edge of the pad. Please refer to Topo D.
- $\pm 3,270$ ' (0.62 miles) –New 16" buried gas pipeline from the edge of the pad to the proposed 36I intersection. Please refer to Topo D.

The total liquid gathering pipeline distance from the separator to the tie in point is  $\pm 3,760$ ' and the individual segments are broken up as follows:

- ±40' (0.01 miles) –New 6" buried liquid pipeline from the separator to the 36C intersection. Please refer to Topo D2.
- $\pm 450$ ' (0.09 miles) –New 6" buried liquid pipeline from the 36 C intersection to the edge of the pad. Please refer to Topo D.
- ±3,270' (0.62 miles) –New 6" buried liquid pipeline from the edge of the pad to the proposed 36I intersection. Please refer to Topo D.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

The proposed pipelines will be buried and will include gas gathering and liquid gathering pipelines in the same trench. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. KMG requests a permanent 30' right-of-way adjacent to the road for life-of-project for maintenance, repairs, and/or upgrades, no additional right-of-way will be needed beyond the 30'. Where the pipeline is not adjacent to the road or well pad, KMG requests a temporary 45' construction right-of-way and 30' permanent right-of-way.

The proposed trench width for the pipeline would range from 18-48 inches and will be excavated to a depth of 48 to 60 inches of normal soil cover or 24 inches of cover in consolidated rock. During construction blasting may occur along the proposed right-of-way where trenching equipment cannot cut into the bedrock. Large debris and rocks removed from the earth during trenching and blasting that could not be returned to the trench would be distributed evenly and naturally in the project area. The proposed pipelines will be pressure tested pneumatically (depending on size) or with fluids (either fresh or produced). If fluids are used, there will be no discharge to the surface.

NBU 922-36A1CS / 36B1CS/ 36B4BS/ 36G1BS

Surface Use Plan of Operations Page 4

Pipeline signs will be installed along the right-of-way to indicate the pipeline proximity and ownership, as well as to provide emergency contact phone numbers. Above ground valves, T's, and/or cathodic protection will be installed at various locations for connection, corrosion prevention and/or for safety purposes.

# D. <u>Location and Type of Water Supply:</u>

Water for drilling purposes will be obtained from one of the following sources:

- Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.
- Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

# **E.** Source of Construction Materials:

Construction operations will typically be completed with native materials found on location. If needed, construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source and described in subsequent Sundry requests. No construction materials will be removed from State lands without prior approval from SITLA.

# F. Methods of Handling Waste Materials:

Should the well be productive, produced water will be contained in a water tank and will be transported by pipeline and/or truck to an approved disposal sites facilities and/or Salt Water Disposal (SWD) injection well. Currently, those facilities are:

RNI in Sec. 5 T9S R22E

Ace Oilfield in Sec. 2 T6S R20E

MC&MC in Sec. 12 T6S R19E

Pipeline Facility in Sec. 36 T9S R20E

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

Ouray #1 SWD in Sec. 1 T9S R21E

NBU 159 SWD in Sec. 35 T9S R21E

CIGE 112D SWD in Sec. 19 T9S R21E

CIGE 114 SWD in Sec. 34 T9S R21E

NBU 921-34K SWD in Sec. 34 T9S R21E

NBU 922-36A1CS / 36B1CS/ 36B4BS/ 36G1BS

**Surface Use Plan of Operations Page 5** 

NBU 921-33F SWD in Sec. 33 T9S R21E NBU 921-34L SWD in Sec. 34 T9S R21E

Drill cuttings and/or fluids will be contained in the reserve/frac pit. Cuttings will be buried in pit(s) upon closure. Unless otherwise approved, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface runoff. Should fluid hydrocarbons be encountered during drilling, completions or well testing, product will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by SITLA. Should timely removal prove infeasible, the pit will be netted with mesh no larger than 1 inch until such time as hydrocarbons can be removed. Hydrocarbon removal will also take place prior to the closure of the pit, unless authorization is provided for disposal via alternative pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with a synthetic material 20-mil or thicker, The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

For the protection of livestock and wildlife, all open pits and cellars will be fenced/covered to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after six (6) months from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Additional drying methods may include fly-ash solidification or sprinkler evaporation. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift. Reserve pit liners will be cut off or folded as near to the mud surface as possible and as safety considerations allow and buried on location.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly,

#### NBU 922-36A1CS / 36B1CS/ 36B4BS/ 36G1BS

Surface Use Plan of Operations Page 6

and transported to an approved disposal facility.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Any undesirable event, including accidental release of fluids, or release in excess of reportable quantities, will be managed according to the notification requirements of UDOGMs "Reporting Oil and Gas Undesirable Events" rule. Where State wells are participatory to a Federal agreement, according to NTL-3A, the appropriate Federal agencies will be notified.

#### **Materials Management**

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities and may be kept in limited quantities on drilling sites and well locations for short periods of time during drilling or completion activities.

#### G. <u>Ancillary Facilities</u>:

None are anticipated.

#### H. Well Site Layout (see Well Pad Design Summary):

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit, access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project where applicable. Site-specific conditions may require slight deviation in actual equipment and facility layout; however, the area of disturbance, as described in the survey, will not be exceeded.

Coordinates are provided in the National Spatial Reference System, North American Datum, 1927 (NAD27) or latest edition. Distances are depicted on each plat to the nearest two adjacent section lines.

#### I. <u>Plans for Reclamation of the Surface</u>:

#### NBU 922-36A1CS / 36B1CS/ 36B4BS/ 36G1BS

Surface Use Plan of Operations Page 7

Surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. This reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but are not limited to: re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

#### **Interim Reclamation**

Interim reclamation includes pit closure, re-contouring (where possible), soil bed preparation, topsoil placement, seeding, and/or weed control.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit.

#### **Final Reclamation**

Final reclamation will be performed for newly drilled unproductive wells and/or at the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by KMG. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring, final grading will be conducted over the entire

#### NBU 922-36A1CS / 36B1CS/ 36B4BS/ 36G1BS

Surface Use Plan of Operations Page 8

surface of the well site and access road. Where practical, the area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers and surface materials will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep perpendicular to the natural flow of water.

All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded.

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to UDOGM.

#### Seeding and Measures Common to Interim and Final Reclamation

Reclaimed areas may be fenced to exclude grazing and encourage re-vegetation.

On slopes where severe erosion can become a problem and the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. The slope will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to, erosion control blankets and bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Seeding will occur year-round as conditions allow. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for revegetation. The site specific seed mix will be provided by SITLA.

#### J. Surface/Mineral Ownership:

SITLA 675 East 500 South, Suite 500 Salt Lake City, UT 84102

#### **K.** Other Information:

None

#### NBU 922-36A1CS / 36B1CS/ 36B4BS/ 36G1BS

Surface Use Plan of Operations

Page 9

#### M. <u>Lessee's or Operators' Representative & Certification:</u>

Gina T. Becker Regulatory Analyst II Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6086 Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage for State lease activities is provided by State Surety Bond 22013542, and for applicable Federal lease activities and pursuant to 43 CFR 3104, by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Gina T. Becker

May 9, 2011

Date



JOE JOHNSON LANDMAN KERR-MCGEE ONSHORE OIL & GAS, L.P. 1099 18TH STREET, SUITE 1800, DENVER, CO 80202 720-929-6708 • FAX 720-929-7708 E-MAIL: JOE.JOHNSON@ANADARKO.COM

April 13, 2011

Ms. Diana Mason Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11 NBU 922-36B1CS

T9S-R22E

Section 36: NWNE/NWNE Surface: 674' FNL, 2282' FEL Bottom Hole: 579' FNL, 1821' FEL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.


- Kerr-McGee's NBU 922-36B1CS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire
  directional well bore.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joseph D. Johnson Landman



## **United States Department of the Interior**

#### **BUREAU OF LAND MANAGEMENT**

Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

May 20, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2011 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Natural Buttes Unit, Uintah County, Utah.

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

#### NBU 922-36I PAD

43-047-51586	NBU	922-36H4BS BHL		 R22E R22E	_	
43-047-51587	NBU	922-36H4CS BHL		R22E R22E		
43-047-51588	NBU	922-36I1CS BHL		R22E R22E		
43-047-51589 NBU 922-36K PAI		922-36I4CS BHL		 R22E R22E	_	
		922-36K1BS BHL		 R22E R22E	_	
43-047-51591	NBU	922-36K1CS BHL		 R22E R22E	_	
43-047-51592	NBU	922-36K4BS BHL		 R22E R22E	_	
43-047-51593	NBU	922-36K4CS BHL		 R22E R22E	_	
43-047-51594	NBU	922-36L4CS BHL		R22E R22E		

Page 2

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE

NRII	922	-36N	PAD
NDU	JLL	-JUIN	FAU

NBU 922-36N PAI	)						
43-047-51595	NBU	922-36M1CS BHL				2379 0816	
43-047-51596	NBU	922-36M4CS BHL			_	2379 0819	
43-047-51597	NBU	922-36N1BS BHL			_	2379 2140	
43-047-51598	NBU	922-36N4CS BHL			_	2379 2081	
43-047-51599	NBU	922-3604CS BHL			_	2379 1814	
NBU 922-360 PA	D						
43-047-51600	NBU	922-36J1CS BHL			_	2113 1809	
43-047-51601	NBU	922-36J4BS BHL	 	 	 	2094 1816	
43-047-51602	NBU		 	 	 	2075 1816	
43-047-51603	NBU				_	2085 1815	
		922-3604BS BHL			_	2103 1814	
NBU 922-36P PAI	)						
43-047-51605	NBU	922-36P1BS BHL			_	0606 0493	
43-047-51606	NBU	922-36P1CS BHL				0611 0493	
43-047-51607	NBU	922-36P4BS BHL					
		922-36P4CS BHL					
NBU 922-36B PAI							
43-047-51609	NBU	922-36A1CS BHL				2273 0494	
43-047-51610	NBU	922-36B1CS BHL				2282 1821	
43-047-51611	NBU	922-36B4BS BHL				2264 1828	

Page 3

API # WELL NAME LOCATION (Proposed PZ WASATCH-MESA VERDE BHL Sec 36 T09S R22E 1439 FNL 1861 FEL **NBU 922-36C PAD** 43-047-51613 NBU 922-36C1CS Sec 36 T09S R22E 0700 FNL 1741 FWL BHL Sec 36 T09S R22E 0485 FNL 2152 FWL 43-047-51614 NBU 922-36C4BS Sec 36 T09S R22E 0706 FNL 1749 FWL BHL Sec 36 T09S R22E 0746 FNL 2153 FWL 43-047-51615 NBU 922-36F1BS Sec 36 T09S R22E 0718 FNL 1765 FWL BHL Sec 36 T09S R22E 1407 FNL 2151 FWL BHL Sec 36 T09S R22E 1738 FNL 2150 FWL **NBU 922-36D PAD** 43-047-51617 NBU 922-36D1CS Sec 36 T09S R22E 1062 FNL 0981 FWL BHL Sec 36 T09S R22E 0579 FNL 0825 FWL 43-047-51618 NBU 922-36D4BS Sec 36 T09S R22E 1060 FNL 0971 FWL BHL Sec 36 T09S R22E 0910 FNL 0825 FWL 43-047-51619 NBU 922-36D4CS Sec 36 T09S R22E 1064 FNL 0990 FWL BHL Sec 36 T09S R22E 1241 FNL 0825 FWL 43-047-51620 NBU 922-36E1BS Sec 36 T09S R22E 1067 FNL 1000 FWL BHL Sec 36 T09S R22E 1572 FNL 0825 FWL **NBU 922-36E PAD** BHL Sec 36 T09S R22E 1903 FNL 0824 FWL BHL Sec 36 T09S R22E 2245 FNL 0818 FWL BHL Sec 36 T09S R22E 2565 FNL 0824 FWL BHL Sec 36 T09S R22E 2401 FSL 0824 FWL **NBU 922-36G3 PAD** 43-047-51625 NBU 922-36F4BS Sec 36 T09S R22E 2414 FNL 2443 FEL BHL Sec 36 T09S R22E 2070 FNL 2149 FWL 43-047-51626 NBU 922-36F4CS Sec 36 T09S R22E 2424 FNL 2445 FEL BHL Sec 36 T09S R22E 2401 FNL 2149 FWL 43-047-51627 NBU 922-36G4BS Sec 36 T09S R22E 2405 FNL 2441 FEL BHL Sec 36 T09S R22E 2235 FNL 1818 FEL 

BHL Sec 36 T09S R22E 2566 FNL 1818 FEL

Page 4

This office has no objection to permitting the wells at this time.

Digitally signed by Michael L. Coulthard Michael L. Coulthard

Management, ou=Branch of Minerals, email=Michael\_Coulthard@blm.gov, c=US
Date: 2011.05.23 07:16:05-06'00'

bcc: File - Natural Buttes Unit

Division of Oil Gas and Mining

Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:5-20-11

From: Jim Davis

To: Bonner, Ed; Garrison, LaVonne; Hill, Brad; Mason, Diana

CC: Gina Becker; Lytle, Andy Date: 6/8/2011 3:00 PM

Subject: Kerr McGee APD approvals.

The following APDs have been approved by SITLA including arch and paleo clearance.

```
4304751586
             NBU 922-36H4BS
4304751587
             NBU 922-36H4CS
4304751588
             NBU 922-36I1CS
4304751589
             NBU 922-36I4CS
4304751590
             NBU 922-36K1BS
4304751591
             NBU 922-36K1CS
4304751592
             NBU 922-36K4BS
4304751593
             NBU 922-36K4CS
4304751594
             NBU 922-36L4CS
4304751595
             NBU 922-36M1CS
4304751596
             NBU 922-36M4CS
4304751597
             NBU 922-36N1BS
             NBU 922-36N4CS
4304751598
4304751599
             NBU 922-36O4CS
4304751600
             NBU 922-36J1CS
             NBU 922-36J4BS
4304751601
4304751602
             NBU 922-36J4CS
4304751603
             NBU 922-3601BS
4304751604
             NBU 922-36O4BS
4304751605
             NBU 922-36P1BS
4304751606
             NBU 922-36P1CS
4304751607
             NBU 922-36P4BS
4304751608
             NBU 922-36P4CS
4304751613
             NBU 922-36C1CS
4304751614
             NBU 922-36C4BS
4304751615
             NBU 922-36F1BS
             NBU 922-36F1CS
4304751616
             NBU 922-36D1CS
4304751617
4304751618
             NBU 922-36D4BS
4304751619
             NBU 922-36D4CS
4304751620
             NBU 922-36E1BS
4304751621
             NBU 922-36E1CS
4304751622
             NBU 922-36E4BS
4304751623
             NBU 922-36E4CS
4304751624
             NBU 922-36L1BS
4304751625
             NBU 922-36F4BS
4304751626
             NBU 922-36F4CS
4304751627
             NBU 922-36G4BS
4304751628
             NBU 922-36G4CS
```

Full paleo monitoring is a required condition for the approval of these APDs- as recommended in the paleo report.

```
4304751609
            NBU 922-36A1CS
4304751610
            NBU 922-36B1CS
4304751611
            NBU 922-36B4BS
4304751612
            NBU 922-36G1BS
```

Thanks.

-Jim


Jim Davis Utah Trust Lands Administration jimdavis1@utah.gov Phone: (801) 538-5156

#### BOPE REVIEW KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 922-36B1CS 43047516100000

Well Name		KERR-MCGE	EE	OIL & GAS ON	SHORE	, L.P. NBI	U 922-36B1C	<u>s</u>
String		Surf	Ī	Prod				
Casing Size(")		8.625	1	4.500				
Setting Depth (TVD)		2333	1	8800				
Previous Shoe Setting Dept	th (TVD)	40	1	2333				<u>-</u>
Max Mud Weight (ppg)		8.4	1	12.5				<u> </u>
BOPE Proposed (psi)		500	1	5000			<u> </u>	1
Casing Internal Yield (psi)		3390	1	7780				<u> </u>
Operators Max Anticipated	d Pressure (psi)	5632	1	12.3			<u>,                                    </u>	1
			_	,	-			
Calculations	Suri	f String	_	5 4 th m	+	8.625	5 "	
Max BHP (psi)		.052*Sett	ın	g Depth*MW	/= 10/	19	DODE 4	L C D W A LG C C A D GO
MASP (Gas) (psi)	Max	, DUD (0.12:	*0	Setting Depth)				dequate For Drilling And Setting Casing at Depth?
			_				NO	air drill
MASP (Gas/Mud) (psi)	Max	K BHP-(0.22)	* 2	Setting Depth)	)=  506	6	NO Con For	OK
Pressure At Previous Shoe	May RHP- 22*(Setting D	enth - Previo	N116	s Shoe Denth				ll Expected Pressure Be Held At Previous Shoe?
Required Casing/BOPE To		eptii - i ievio	, u.	s snoc Depui,			NO psi	Reasonable for area
*Max Pressure Allowed @			_		233	33	-	
"Max Fressure Allowed @	Frevious Casing Shoe-		_		40		psi *As	ssumes 1psi/ft frac gradient
Calculations	Prod	l String				4.500	"	
Max BHP (psi)		.052*Sett	in	g Depth*MW	7= 572	20		
							BOPE A	dequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max	k BHP-(0.12	*5	Setting Depth)	<b>)</b> =  466	64	YES	
MASP (Gas/Mud) (psi)	Max	BHP-(0.22	*5	Setting Depth)	<b>)=</b> 378	34	YES	OK
							*Can Ful	ll Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting De	epth - Previo	ous	s Shoe Depth)	)= 429	97	NO	Reasonable
Required Casing/BOPE Te	est Pressure=				500	00	psi	
*Max Pressure Allowed @	Previous Casing Shoe=				233	33	psi *As	ssumes 1psi/ft frac gradient
Calculations	S	tring	_		$\overline{}$		"	
Max BHP (psi)			in	g Depth*MW	/=		i	
							BOPE A	dequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max	BHP-(0.12	*5	Setting Depth)	= _		NO	
MASP (Gas/Mud) (psi)	Max	BHP-(0.22	*5	Setting Depth)	= =		NO	
							*Can Ful	ll Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting De	epth - Previo	ous	s Shoe Depth)	)=  _		NO	
Required Casing/BOPE Te	est Pressure=						psi	
*Max Pressure Allowed @	Previous Casing Shoe=						psi *As	ssumes 1psi/ft frac gradient
Calculations	C	tring			_		"	
Max BHP (psi)			in	g Depth*MW	/=		1	
(P32)		.002 500		.g z epui iii ii	╬		BOPE AG	dequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max	BHP-(0.12	*5	Setting Depth)	= =		NO	, s s s s s s s s s s s s s s s s s s s
MASP (Gas/Mud) (psi)			_	Setting Depth)	-1-		NO	<u> </u>
, , , ,		`	_		-1!		<u> </u>	ll Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting De	epth - Previo	ous	s Shoe Depth	=		NO	Ī Ī
Required Casing/ROPF To	est Pressure=		_		-1:-		nei	

*Max Pressure Allowed @ Previous Casing Shoe=	psi	*Assumes 1psi/ft frac gradient

## 43047516100000 NBU 922-36B1CS



43047516100000 NBU 922-36B1CS Well name:

Operator: KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type: Surface

Location: **UINTAH** COUNTY Project ID: 43-047-51610

> Fracture depth: Injection pressure:

Design parameters: Minimum design factors: **Environment:** H2S considered? Collapse Collapse: No 74 °F 8.400 ppg Surface temperature: Mud weight: Design factor 1.125 Design is based on evacuated pipe. Bottom hole temperature: 107 °F Temperature gradient: 1.40 °F/100ft Minimum section length: 1,000 ft **Burst:** Design factor 1.00 Cement top: 1,262 ft Burst Max anticipated surface pressure: 2,053 psi Internal gradient: 0.120 psi/ft Tension: Directional Info - Build & Drop Calculated BHP 2,333 psi 8 Round STC: 1.80 (J) Kick-off point 300 ft 8 Round LTC: 1.80 (J) Departure at shoe: 368 ft 1.60 (J) Maximum dogleg: No backup mud specified. **Buttress:** 2 °/100ft Premium: 1.50 (J) Inclination at shoe: 12° Re subsequent strings: Body yield: 1.60 (B) Next setting depth: 8,800 ft Tension is based on air weight. Next mud weight: 12.500 ppg Neutral point: 2,075 ft Next setting BHP: 5,715 psi Fracture mud wt: 19.250 ppg

Run Seq	Segment Length (ft) 2370	Size (in) 8.625	Nominal Weight (lbs/ft) 28.00	<b>Grade</b> I-55	End Finish LT&C	True Vert Depth (ft) 2333	Measured Depth (ft) 2370	Drift Diameter (in) 7.892	Est. Cost (\$) 93852
Run Seq	Collapse Load (psi) 1018	Collapse Strength (psi) 1880	Collapse Design Factor 1.846	Burst Load (psi) 2333	Burst Strength (psi) 3390	Burst Design Factor 1.45	Tension Load (kips) 65.3	Tension Strength (kips) 348	Tension Design Factor 5.33 J

Helen Sadik-Macdonald Prepared Div of Oil, Gas & Mining by:

Phone: 801 538-5357 FAX: 801-359-3940

Date: August 2,2011 Salt Lake City, Utah

2,333 ft

2,333 psi

Remarks:

Collapse is based on a vertical depth of 2333 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Well name:

43047516100000 NBU 922-36B1CS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type:

Production

Project ID: 43-047-51610

Location:

**UINTAH** 

COUNTY

**Environment:** 

Collapse

Mud weight:

Internal fluid density:

Design parameters:

12.500 ppg 1.000 ppg Collapse:

Design factor

Minimum design factors:

1.125

H2S considered?

No 74 °F Surface temperature: Bottom hole temperature: 197 °F Temperature gradient: 1.40 °F/100ft

Minimum section length:

100 ft

Burst:

Design factor

1.00

1.80 (J)

1.80 (J)

1.60 (J)

1.50 (J)

1.60 (B)

Cement top:

796 ft

**Burst** 

Max anticipated surface pressure:

Internal gradient: Calculated BHP

No backup mud specified.

3,778 psi 0.220 psi/ft 5,715 psi

**Tension:** 8 Round STC: 8 Round LTC:

> Buttress: Premium:

Body yield:

Tension is based on air weight. Neutral point: 7,201 ft

Directional Info - Build & Drop Kick-off point 300 ft Departure at shoe: 470 ft Maximum dogleg: 2 °/100ft

Inclination at shoe: o°

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	8845	4.5	11.60	I-80	LT&C	8800	8845	3.875	116754
Run	Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension
Seq	Load (psi)	Strength (psi)	Design Factor	Load (psi)	Strength (psi)	Design Factor	Load (kips)	Strength (kips)	Design Factor
1	5257	6360	1.210	5715	7780	1.36	102.1	212	2.08 J

Helen Sadik-Macdonald Prepared

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: August 2,2011 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 8800 ft, a mud weight of 12.5 ppg. An internal gradient of .052 psi/ft was used for collapse from TD Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

## **ON-SITE PREDRILL EVALUATION**

### Utah Division of Oil, Gas and Mining

**Operator** KERR-MCGEE OIL & GAS ONSHORE, L.P.

Well Name NBU 922-36B1CS

API Number 43047516100000 APD No 3784 Field/Unit NATURAL BUTTES

**Location: 1/4,1/4** NWNE **Sec** 36 **Tw** 9.0S **Rng** 22.0E 674 FNL 2282 FEL

GPS Coord (UTM) 637760 4428557 Surface Owner

#### **Participants**

Floyd Bartlett (DOGM), Sheila Wopsock, Lovell Young, Gina Becker, Mark Koehn, Griz Oleen (Kerr McGee), Ben Williams (UDWR) and Mitch Batty, John Slaugh (Timberline Engineering and Land Surveying).

#### Regional/Local Setting & Topography

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¾ mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 44.4 road miles following Utah State, Uintah County and oilfield development roads to the location.

Four additional gas wells will be added to and directionally drilled from the NBU 922-36B pad. They are the NBU 922-36G1BS, NBU 922-36B1CS, NBU 922-36A1CS and NBU 922-36B4BS. The pad contains the existing NBU 922-36B gas well. The existing pad will be significantly enlarged in all directions. The site is in a small basin surrounded with moderate to steep side-hills except to the southwest. The pad and reserve pit extend onto the steep side-hills to the southeast and south and continue to the west. Some minor rills or swales interrupt this south side hill but a diversion is not warranted. Flow from the basin to the southwest will be re-diverted with a small berm and ditch along the edge of the pad. Where the pad is cut into the steep side slopes, leave the cut slope at about ½:1 to reduce the amount of cutting and disturbance. On the north side of the pad (Corners 11-2) fill will extend across the natural drainage. A diversion ditch is needed along the side slope beyond the pad returning flows to the natural drainage. After the pit is reclaimed, a pond should be considered in the small basin that extends to the southwest beyond corner 9. Excess spoils can be used for the embankment. Maximum cut is 16.2 feet at Pit Corner C and maximum fill is 10.7 feet at Corner 2. The White River is approximately 1 ½ miles to the west. The existing pad shows no stability problems and the site has no significant concerns for constructing an enlarged pad and drilling and operating the planned wells. It is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA.

#### Surface Use Plan

**Current Surface Use** 

Grazing Wildlfe Habitat Existing Well Pad

New Road Miles Well Pad Src Const Material Surface Formation

0 Width 240 Length 440 Onsite UNTA

**Ancillary Facilities** N

#### Waste Management Plan Adequate?

8/3/2011 Page 1

#### **Environmental Parameters**

Affected Floodplains and/or Wetlands N

#### Flora / Fauna

Area beyond the existing pad is poorly vegetated with greasewood, cheatgrass, black sagebrush, broom snakeweed, globemallow, Sitanion hystrix, shadscale, rabbitbrush, loco weed, pepper weed, halogeton and annuals.

Sheep, deer, antelope, coyote, and other small mammals and birds.

#### **Soil Type and Characteristics**

Soils are a shallow rocky sandy loam.

**Erosion Issues** Y

**Sedimentation Issues** Y

Site Stability Issues N

**Drainage Diverson Required?** Y

Berm Required? Y

**Erosion Sedimentation Control Required?** Y

Paleo Survey Run? Y Paleo Potental Observed? N Cultural Survey Run? Y Cultural Resources? N

#### **Reserve Pit**

Site-Specific Factors Site Ranking

Distance to Groundwater (feet)
Distance to Surface Water (feet)
Dist. Nearest Municipal Well (ft)
Distance to Other Wells (feet)
Native Soil Type
Fluid Type
Drill Cuttings
Annual Precipitation (inches)
Affected Populations
Presence Nearby Utility Conduits

Final Score Sensitivity Level

**Characteristics / Requirements** 

Closed Loop Mud Required? Y Liner Thickness 30 Pit Underlayment Required? Y

**Other Observations / Comments** 

Floyd Bartlett 5/24/2011

8/3/2011 Page 2

**Evaluator** Date / Time

8/3/2011 Page 3

## **Application for Permit to Drill Statement of Basis**

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo				Status		Well Type	Surf Ow	ner CBM
3784	430475161000	000			LOCKI	ED	GW	S	No
Operator	KERR-MCGE	EE OI	L & G	iAS	ONSHORI	E, L.P.	<b>Surface Owner-APD</b>		
Well Name	NBU 922-36B	31CS					Unit	NATUR	AL BUTTES
Field	NATURAL B	UTTI	ES				Type of Work	DRILL	
Location	NWNE 36	9S	22E	S	674 FNL	2282 FEL	GPS Coord (UTM)	637740E	4428569N

#### **Geologic Statement of Basis**

8/3/2011

Kerr McGee proposes to set 2,370' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 2,700'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the proposed location . The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The production casing cement should be brought up above the base of the moderately saline ground water in order to isolate it from fresher waters up hole. The proposed casing and cement should adequately protect any usable ground water.

Brad Hill 6/20/2011
APD Evaluator Date / Time

#### **Surface Statement of Basis**

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¾ mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 44.4 road miles following Utah State, Uintah County and oilfield development roads to the location.

Four additional gas wells will be added to and directionally drilled from the NBU 922-36B pad. They are the NBU 922-36G1BS, NBU 922-36B1CS, NBU 922-36A1CS and NBU 922-36B4BS. The pad contains the existing NBU 922-36B gas well. The existing pad will be significantly enlarged in all directions. The site is in a small basin surrounded with moderate to steep side-hills except to the southwest. The pad and reserve pit extend onto the steep side-hills to the southeast and south and continue to the west. Some minor rills or swales interrupt this south side hill but a diversion is not warranted. Flow from the basin to the southwest will be re-diverted with a small berm and ditch along the edge of the pad. Where the pad is cut into the steep side slopes, leave the cut slope at about ½1 to reduce the amount of cutting and disturbance. On the north side of the pad (Corners 11-2) fill will extend across the natural drainage. A diversion ditch is needed along the side slope beyond the pad returning flows to the natural drainage. After the pit is reclaimed, a pond should be considered in the small basin that extends to the southwest beyond corner 9. Excess spoils can be used for the embankment. Maximum cut is 16.2 feet at Pit Corner C and maximum fill is 10.7 feet at Corner 2. The White River is approximately 1 ½ miles to the west. The existing pad shows no stability problems and the site has no significant concerns for constructing an enlarged pad and drilling and operating the planned wells. It is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA. Ed Bonner and Jim Davis of SITLA were invited to attend the pre-site evaluation. Neither attended. SITLA is to be contacted for reclamation standards including a seed mix to be used.

# **Application for Permit to Drill Statement of Basis**

Utah Division of Oil, Gas and Mining

Page 2

Ben Williams of the Utah Division of Wildlife Resources attended the pre-site. Mr. Williams stated no wildlife values would be significantly affected by drilling and operating the additional wells at this location.

Floyd Bartlett 5/24/2011
Onsite Evaluator Date / Time

#### Conditions of Approval / Application for Permit to Drill

**Category** Condition

8/3/2011

Pits A synthetic liner with a minimum thickness of 30 mils with a DOUBLE felt subliner shall be properly installed and

maintained in the reserve pit.

Surface The well site shall be bermed to prevent fluids from leaving the pad.

Surface The reserve pit shall be fenced upon completion of drilling operations.

#### WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 5/13/2011 **API NO. ASSIGNED:** 43047516100000

WELL NAME: NBU 922-36B1CS

**OPERATOR:** KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) **PHONE NUMBER:** 720 929-6086

**CONTACT:** Gina Becker

PROPOSED LOCATION: NWNE 36 090S 220E **Permit Tech Review:** 

> SURFACE: 0674 FNL 2282 FEL **Engineering Review:**

> **BOTTOM:** 0579 FNL 1821 FEL Geology Review:

**COUNTY: UINTAH** 

**LATITUDE: 39.99797 LONGITUDE:** -109.38649

UTM SURF EASTINGS: 637740.00 NORTHINGS: 4428569.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 3 - State

LEASE NUMBER: ML-22650 PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

**SURFACE OWNER: 3 - State COALBED METHANE: NO** 

**RECEIVED AND/OR REVIEWED: LOCATION AND SITING:** 

 PLAT R649-2-3.

Unit: NATURAL BUTTES Bond: STATE/FEE - 22013542

**Potash** R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

**Drilling Unit** Oil Shale 190-13

Board Cause No: Cause 173-14 Water Permit: Permit #43-8496

**Effective Date:** 12/2/1999 **RDCC Review:** 

Siting: Suspends General Siting **Fee Surface Agreement** 

✓ Intent to Commingle R649-3-11. Directional Drill

**Commingling Approved** 

**Comments:** Presite Completed

Stipulations:

3 - Commingling - ddoucet 5 - Statement of Basis - bhill 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason 25 - Surface Casing - hmacdonald

API Well No: 43047516100000



## State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

#### Permit To Drill

\*\*\*\*\*\*

**Well Name:** NBU 922-36B1CS **API Well Number:** 43047516100000

**Lease Number:** ML-22650 **Surface Owner:** STATE **Approval Date:** 8/3/2011

#### **Issued to:**

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

#### **Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

#### **Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

#### **Commingle:**

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

#### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### **Conditions of Approval:**

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

API Well No: 43047516100000

#### **Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan contact Dustin Doucet
- Significant plug back of the well contact Dustin Doucet
- Plug and abandonment of the well contact Dustin Doucet

#### **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well contact Carol Daniels OR
- submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at http://oilgas.ogm.utah.gov
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to cementing or testing casing contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well contact Dan Jarvis

#### **Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 office
- Dustin Doucet 801-538-5281 office

801-733-0983 - after office hours

• Dan Jarvis 801-538-5338 - office

801-231-8956 - after office hours

#### **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) due prior to implementation
- Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
- Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas Sundry Number: 20589 API Well Number: 43047516100000

			FORM 9
	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES		
	DIVISION OF OIL, GAS, AND MINI		<b>5.LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-22650
	RY NOTICES AND REPORTS (		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	sals to drill new wells, significantly deepen e igged wells, or to drill horizontal laterals. Us		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36B1CS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		<b>9. API NUMBER:</b> 43047516100000
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th S	PHON treet, Suite 600, Denver, CO, 80217 3779	<b>E NUMBER:</b> 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0674 FNL 2282 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: NWNE Section: 36	P, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH
11. CHE	CK APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPORT,	OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
□ NOTICE OF INTENT	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	☐ CHANGE WELL NAME
Approximate date work will start:	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN [	FRACTURE TREAT	☐ NEW CONSTRUCTION
Date of work completion:	OPERATOR CHANGE	PLUG AND ABANDON	☐ PLUG BACK
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
✓ SPUD REPORT  Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
11/17/2011	☐ TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT			
Report Date:	☐ WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
	WILDCAT WELL DETERMINATION	OTHER	OTHER:
MIRU PETE MARTIN RAN 14" 36.7# SCHE	MPLETED OPERATIONS. Clearly show all perting BUCKET RIG. DRILLED 20" CC DULE 10 PIPE. CMT W/28 SX R 11/17/2011 AT 1230 HRS	PINDUCTOR HOLE TO 40'. EADY MIX. SPUD WELL O  . Oil FOR	
NAME (PLEASE PRINT) Sheila Wopsock	<b>PHONE NUMBER</b> 435 781-7024	TITLE Regulatory Analyst	
SIGNATURE N/A		<b>DATE</b> 11/22/2011	

## **BLM - Vernal Field Office - Notification Form**

Oper	ator KERR-McGEE OIL & GA	S Rig Name	e/# <u>BUC</u>	KET RIG
	nitted By SHEILA WOPSOCK		nber <u>435</u>	.781.7024
	Name/Number NBU 922-36E			\
	Qtr <u>NW/NE</u> Section 36	rownsnip <u>s</u>	<u> </u>	Range <u>22E</u>
	e Serial Number ML-22650			
API I	Number <u>4304751610</u>		1818)	
*	<u>l Notice</u> – Spud is the initial pelow a casing string.	spudding o	f the we	ell, not drilling
	Date/Time <u>11/17/2011</u>	1400 HRS	AM 🔽	РМ
Casir time: ✓	ng – Please report time cas s. Surface Casing Intermediate Casing Production Casing Liner Other	ing run star	ts, not c	ementing
	Date/Time <u>12/04/2011</u>	0800 HRS	AM 🔽	РМ
BOPI	E Initial BOPE test at surface BOPE test at intermediate 30 day BOPE test Other	<b>–</b> 1		RECEIVED NOV 1 6 2011 DRY OF OIL, GAS & MINING
	Date/Time		АМ 🗌	РМ
Rem	arks ESTIMATED DATE AND LOVEL YOUNG AT 435.7	TIME. PLEA <del>781.7051 FO</del>	SE CON <sup>-</sup> <del>R MORE</del>	TACT <b>±</b>

#### STATE OF UTAH **DEPARTMENT OF NATURAL RESOURCES** DIVISION OF OIL, GAS AND MINING

#### **ENTITY ACTION FORM**

Operator:

KERR McGEE OIL & GAS ONSHORE LP

Operator Account Number: N 2995

Address:

1368 SOUTH 1200 EAST

city VERNAL

state UT zip 84078 Phone Number: (435) 781-7024

Well 1

API Number	Well N	lame	QQ	Sec	Twp	Rng	County		
4304751612	NBU 922-36G1BS		NWNE	36	98	22E	UINTAH		
Action Code	Current Entity Number	New Entity Number	s	Spud Date			Entity Assignment Effective Date		
$\overline{\mathcal{B}}$	99999	3900	1	1/19/20	11	11	130/11		
	U PETE MARTIN BUCKE	TRIG. WSM			Cist		150/1		

SPUD WELL ON 11/19/2011 AT 1400 HRS.

RHC-SWNE

Well 2

API Number	Well N	lame	QQ	Sec	Twp	Rng	County
4304751610	NBU 922-36B1CS		NWNE	36	98	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	S	Spud Date		Entity Assignn Effective Da	
B	99999	2900	1	1/17/20	11	11/	30/11
	J PETE MARTIN BUCKE D WELL ON 11/17/2011	TRIG. WSM		1/17/20	11	11/	30/

Well 3

API Number	Well I	Vame	QQ	Sec	Twp	Rng	County
4304751609	NBU 922-36A1CS		NWNE	36	98	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	S	pud Da	te		ty Assignment fective Date
$\mathcal{B}$	99999	3900	1	1/20/20	11	11	130/11
	U PETE MARTIN BUCKE D WELL ON 11/20/2011	T RIG. WS 7. AT 1330 HRS.	NVD BHL=	· NE	ENE		<i></i>

#### **ACTION CODES:**

- A Establish new entity for new well (single well only)
- B Add new well to existing entity (group or unit well)
- C Re-assign well from one existing entity to another existing entity
- D Re-assign well from one existing entity to a new entity

SHEILA WOPSOCK

Name (Please Print)

Title

Signature **REGULATORY ANALYST** 

11/22/2011

Date

E - Other (Explain in 'comments' section)

RECEIVED

(5/2000) NOV 2 2 2011

	FORM 9			
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING			5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650	
SUNDR	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
Do not use this form for pro current bottom-hole depth, I FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 922-36B1CS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	9. API NUMBER: 43047516100000			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	h Street, Suite 600, Denver, CO, 8021	<b>PHONE NUMBER:</b> 17 3779 720 929-	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0674 FNL 2282 FEL			COUNTY: UINTAH	
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 36 Township: 09.0S Range: 22.0E Meridian: S			STATE: UTAH	
11. CHECI	K APPROPRIATE BOXES TO INDICA	ATE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA	
TYPE OF SUBMISSION	TYPE OF ACTION			
	ACIDIZE	ALTER CASING	CASING REPAIR	
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME	
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE	
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION	
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK	
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION	
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON	
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL	
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION	
1/21/2012		OTHER	OTHER:	
	WILDCAT WELL DETERMINATION	U OTHER	<u> </u>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  MIRU AIR RIG ON JAN. 17, 2012. DRILLED SURFACE HOLE TO 2560'.  RAN SURFACE CASING AND CEMENTED. WELL IS WAITING ON ROTARY RIG. DETAILS OF CEMENT JOB WILL BE INCLUDED WITH WELL  COMPLETION REPORT.  COMPLETION REPORT.  Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONL  January 23, 2012				
NAME (0) 5-205 5-33-33		DED TITLE		
NAME (PLEASE PRINT) Jaime Scharnowske	<b>PHONE NUM</b> 720 929-6304	BER TITLE Regulartory Analyst		
SIGNATURE N/A		<b>DATE</b> 1/23/2012		

	FORM 9			
ı	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650			
SUNDR	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
Do not use this form for pro current bottom-hole depth, I FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36B1CS	
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON		<b>9. API NUMBER:</b> 43047516100000		
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	PHO n Street, Suite 600, Denver, CO, 80217 377	ONE NUMBER: 720 929-6	9. FIELD and POOL or WILDCAT: 5NATURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0674 FNL 2282 FEL			COUNTY: UINTAH	
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NWNE Section: 3	HIP, RANGE, MERIDIAN: 36 Township: 09.0S Range: 22.0E Meridian:	: S	STATE: UTAH	
11. CHECI	K APPROPRIATE BOXES TO INDICATE N	IATURE OF NOTICE, REPOR	T, OR OTHER DATA	
TYPE OF SUBMISSION	TYPE OF ACTION			
7	ACIDIZE	ALTER CASING	CASING REPAIR	
NOTICE OF INTENT Approximate date work will start:  1/17/2012	✓ CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME	
1/17/2012	☐ CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE	
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION	
Date of Work Completion.	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK	
 	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION	
SPUD REPORT Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON	
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL	
DRILLING REPORT Report Date:	☐ WATER SHUTOFF ☐	SI TA STATUS EXTENSION	APD EXTENSION	
кероп расе.	WILDCAT WELL DETERMINATION	OTHER	OTHER:	
12. DESCRIBE PROPOSED OR	COMPLETED OPERATIONS. Clearly show all pe	ertinent details including dates, d	epths, volumes, etc.	
The Operator re Specifically, the O loop drilling option, of the previously as	Approved by the Utah Division of Oil, Gas and Mining Date: February 02, 2012			
of the previously approved drilling plan will not change. Please see the attachment. Thank you.			Date: February 02, 2012	
By: Ust Clut				
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE		
Jaime Scharnowske	720 929-6304	Regulartory Analyst		
SIGNATURE N/A		DATE 1/17/2012		

NBU 922-36B1CS Drilling Program
1 of 7

#### Kerr-McGee Oil & Gas Onshore. L.P.

#### NBU 922-36B1CS

Surface: 674 FNL / 2282 FEL NWNE BHL: 579 FNL / 1821 FEL NWNE

Section 36 T9S R22E

Uintah County, Utah Mineral Lease: ML-22650

#### ONSHORE ORDER NO. 1

#### **DRILLING PROGRAM**

#### 1. & 2. <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1271'	
Birds Nest	1,563'	Water
Mahogany	1,915'	Water
Wasatch	4,377'	Gas
Mesaverde	6,573'	Gas
MVU2	7,559'	Gas
MVL1	8,155'	Gas
TVD	8,800'	
TD	8,845'	

#### 3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Drilling Program

#### 4. Proposed Casing & Cementing Program:

Please refer to the attached Drilling Program

#### 5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

#### 6. <u>Evaluation Program</u>:

Please refer to the attached Drilling Program

NBU 922-36B1CS Drilling Program
2 of 7

#### 7. **Abnormal Conditions:**

Maximum anticipated bottom hole pressure calculated at 8800' TVD, approximately equals 5,632 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,684 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

#### 8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

#### 9. <u>Variances:</u>

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- · Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

#### **Background**

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

NBU 922-36B1CS Drilling Program
3 of 7

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

#### Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

#### **Variance for Mud Material Requirements**

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

#### Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 922-36B1CS Drilling Program
4 of 7

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

#### Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

#### Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

#### 10. Other Information:


Please refer to the attached Drilling Program.


RECEIVED: Jan. 17, 2012

NBU 922-36B1CS Drilling Program 5 of 7



## KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM





Sundry Number: 22311 API Well Number: 43047516100000

NBU 922-36B1CS Drilling Program
6 of 7



#### KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

CONDUCTOR

**PRODUCTION** 

									LTC	DQX
SIZE	INTE	RVAL		WT.	GR.	CPLG.	BURST	COLL	APSE	TENSION
14"	0	-40'								
							3,390	1,880	348,000	N/A
8-5/8"	0	to	2,370	28.00	IJ-55	LTC	2.28	1.69	5.99	N/A
							7,780	6,350	223,000	267,035
4-1/2"	0	to	5,000	11.60	I-80	DQX	1.11	1.11		3.22
4-1/2"	5,000	to	8,845'	11.60	I-80	LTC	1.11	1.11	6.18	

#### **Surface Casing:**

(Burst Assumptions: TD =

12.5 ppg)

0.73 psi/ft = frac gradient @ surface shoe

**DESIGN FACTORS** 

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 70

7000 psi)

0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### **CEMENT PROGRAM**

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGH	łT	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80		1.15
Option 1		+ 0.25 pps flocele					
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80		1.15
		+ 2% CaCl + 0.25 pps flocele					
SURFACE		NOTE: If well will circulate water	to surface,	option 2 wi	ll be utilized		
Option 2 LEAD	1,870'	65/35 Poz + 6% Gel + 10 pps gilsonite	170	35%	11.00		3.82
		+ 0.25 pps Flocele + 3% salt BWOW					
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80		1.15
		+ 0.25 pps flocele					
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80		1.15
PRODUCTION LEAD	3,875'	Premium Lite II +0.25 pps	310	35%	12.00		3.38
		celloflake + 5 pps gilsonite + 10% gel					
		+ 0.5% extender					
TAIL	4,970'	50/50 Poz/G + 10% salt + 2% gel	1,180	35%	14.30		1.31
		+ 0.1% R-3					

<sup>\*</sup>Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

#### FLOAT EQUIPMENT & CENTRALIZERS

SURFACE

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

**PRODUCTION** 

Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well.

1 centralizer on the first 3 joints and one every third joint thereafter.

#### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Nick Spence / Danny Showers / Chad Loesel

DRILLING SUPERINTENDENT:

Kenny Gathings / Lovel Young

DATE:


DATE:

RECEIVED: Jan. 17, 2012

<sup>\*</sup>Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

Drilling Program 7 of 7

# EXHIBIT A NBU 922-36B1CS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK

Sundry Number: 22311 API Well Number: 43047516100000

#### Requested Drilling Options:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

RECEIVED: Jan. 17, 2012

Sundry Number: 23341 API Well Number: 43047516100000

	STATE OF UTAH		FORM 9
ı	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MINI		5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650
SUNDR	RY NOTICES AND REPORTS C	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	oposals to drill new wells, significantly d reenter plugged wells, or to drill horizon n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36B1CS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		<b>9. API NUMBER:</b> 43047516100000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	h Street, Suite 600, Denver, CO, 80217	<b>PHONE NUMBER:</b> 3779 720 929-6	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0674 FNL 2282 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	<b>HIP, RANGE, MERIDIAN:</b> 36 Township: 09.0S Range: 22.0E Meridi	an: S	STATE: UTAH
11. CHECI	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
✓ DRILLING REPORT	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
Report Date: 2/24/2012		☐ SITA STATUS EXTENSION	
	WILDCAT WELL DETERMINATION	OTHER	OTHER:
MIRU ROTARY RI FEBRUARY 22, 2011 CASING. RELEASE HRS. DETAILS OF	COMPLETED OPERATIONS. Clearly show all IG. FINISHED DRILLING FROM 2. RAN 4-1/2" 11.6# I-80. CEM D ENSIGN 138 RIG ON FEBRUF CEMENT JOB WILL BE INCLUE EPORT. WELL IS WAITING ON FACTIVITIES.	1 2,560' TO 8,873' ON IENTED PRODUCTION ARY 24, 2012 @ 03:00 DED WITH THE WELL	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 02, 2012
NAME (PLEASE PRINT)	PHONE NUMBE		
Jaime Scharnowske	720 929-6304	Regulartory Analyst	
SIGNATURE N/A		<b>DATE</b> 2/26/2012	

# State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# Ensign 138 Submitted By DALTON KING Phone Number 435- 828-0982 Well Name/Number NBU 922-36 1CS Qtr/Qtr NW/NE Section 36 Township 9S Range 22E Lease Serial Number ML-22650 API Number43-047-51610	
<u>Casing</u> – Time casing run starts, not cementing times.	
Production Casing Other	
Date/Time <u>2/23/2012</u> <u>08:00</u> AM ⊠ PM □	
BOPE Initial BOPE test at surface casing point Other	
Date/Time AM PM RECEIVE	D
Rig Move Location To: DIV. OF OIL, GAS & MII	•
Date/Time AM DM PM D	
Remarks TIME IS ESTIMATED	

Sundry Number: 25108 API Well Number: 43047516100000

	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOUR DIVISION OF OIL, GAS, AND MI		5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650
SUNDR	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	oposals to drill new wells, significantly reenter plugged wells, or to drill horizon n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36B1CS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	NSHORE, L.P.		9. API NUMBER: 43047516100000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	h Street, Suite 600, Denver, CO, 8021	<b>PHONE NUMBER:</b> 7 3779 720 929-0	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0674 FNL 2282 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 36 Township: 09.0S Range: 22.0E Mer	ridian: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
SPUD REPORT	✓ PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT     Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
4/24/2012	WILDOAT WELL DETERMINATION	OTHER	OTHER:
	WILDCAT WELL DETERMINATION	□ OTHER	<u> </u>
THE SUBJECT WELL 12:50 P.M. THE CHF	COMPLETED OPERATIONS. Clearly show WAS PLACED ON PRODUCT RONOLOGICAL WELL HISTOF TH THE WELL COMPLETION F	TION ON APRIL 24,2012 AT RY WILL BE SUBMITTED	
NAME (PLEASE PRINT) Gina Becker	PHONE NUMI 720 929-6086	BER TITLE Regulatory Analyst II	
SIGNATURE		DATE	
N/A		4/26/2012	

#### STATE OF UTAH AMENDED REPORT FORM 8 DEPARTMENT OF NATURAL RESOURCES (highlight changes) 5. LEASE DESIGNATION AND SERIAL NUMBER: DIVISION OF OIL, GAS AND MINING ML-22650 6. IF INDIAN, ALLOTTEE OR TRIBE NAME WELL COMPLETION OR RECOMPLETION REPORT AND LOG 1a. TYPE OF WELL: 7. UNIT or CA AGREEMENT NAME OIL OTHER UTU63047A b. TYPE OF WORK: 8. WELL NAME and NUMBER: DIFF. RESVR. RE-ENTRY NBU 922-36B1CS 2. NAME OF OPERATOR: 9. API NUMBER: KERR MCGEE OIL & GAS ONSHORE, L.P. 4304751610 3. ADDRESS OF OPERATOR: PHONE NUMBER: 10 FIELD AND POOL, OR WILDCAT STATE CO ZIP 80217 P.O.BOX 173779 CITY DENVER (720) 929-6000 NATURAL BUTTES 4. LOCATION OF WELL (FOOTAGES) 11. QTR/QTR, SECTION, TOWNSHIP, RANGE, AT SURFACE: NWNE 674 FNL 2282 FEL S36, T9S, R22E NWNE 36 9S 22E S AT TOP PRODUCING INTERVAL REPORTED BELOW: NWNE 566 FNL 1817 FEL S36.T9S.R22E 12. COUNTY 13. STATE AT TOTAL DEPTH: NWNE 587 FNL 1818 FEL S36, T9S, R22E BHL 61 HSM UTAH **UINTAH** 17. ELEVATIONS (DF, RKB, RT, GL): 14. DATE SPUDDED: 15. DATE T.D. REACHED: 16. DATE COMPLETED: ABANDONED READY TO PRODUCE V 11/17/2011 2/22/2012 4/24/2012 5015 GL 19. PLUG BACK T.D.: MD 8.804 18. TOTAL DEPTH: MD 8.873 20. IF MULTIPLE COMPLETIONS, HOW MANY? \* 21. DEPTH BRIDGE MD TVD 8,831 TVD 8,762 TVD 22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) 23. ио 🔽 WAS WELL CORED? YES (Submit analysis) HDIL/ZDL/CNGR-BHV-CBL/CMI/GR/CCL WAS DST RUN? NO 🗸 YES (Submit report) YES 🗸 DIRECTIONAL SURVEY? NO (Submit copy) 24. CASING AND LINER RECORD (Report all strings set in well) STAGE CEMENTER CEMENT TYPE & NO. OF SACKS SLURRY VOLUME (BBL) HOLE SIZE SIZE/GRADE WEIGHT (#/ft.) TOP (MD) BOTTOM (MD) CEMENT TOP \*\* AMOUNT PULLED 20" 14" STL 36.7# 0 40 28 11" J-55 28# 0 2,523 675 8 5/8 0 7 7/8" 4 1/2' 1-80 11.6# 0 8,850 1,775 700 25. TUBING RECORD SIZE DEPTH SET (MD) PACKER SET (MD) SIZE DEPTH SET (MD) PACKER SET (MD) SIZE DEPTH SET (MD) PACKER SET (MD) 2 3/8" 8,163 26. PRODUCING INTERVALS 27. PERFORATION RECORD FORMATION NAME TOP (MD) BOTTOM (MD) TOP (TVD) BOTTOM (TVD) NO. HOLES PERFORATION STATUS INTERVAL (Top/Bot - MD) (A) WASATCH 5.994 6.000 5.994 0.36 24 Open 🚺 Squeezed 6.000

(C) Open Squeezed C

(D) Open Squeezed C

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL AMOUNT AND TYPE OF MATERIAL

6584-8785 PUMP 7,692 BBLS SLICK H2O & 152,099 LBS 30/50 OTTAWA SAND

PERF'D 9 STAGES; FRAC'D 8 STAGES

DIV OF OIL GAS & MINING

6.584

0.36

195

Open

Squeezed

8.785

**MESAVERDE** 

(B)

6.584

8,785

31. INITIAL PRO						TERVAL A (As sho				······································	
DATE FIRST PR		TEST DA			HOURS TESTE		TEST PRODUCTIO		GAS - MCF:	WATER - BBL:	PROD. METHOD:
4/24/2012		4/25/			24			0	2,041	580	
20/64	TBG. PRESS 1,577			AVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTIO RATES: →	OIL - BBL:	GAS - MCF: 2,041	WATER - BBL: 580	INTERVAL STATUS PROD
					IN-	TERVAL B (As sho	wn in Item #26)				
DATE FIRST PR	RODUCED:	TEST DA	TE:				TEST PRODUCTIO RATES: →	N OIL-BBL:	GAS MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS	S. CSG. PRI	ESS. API GR	AVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS MCF:	WATER - BBL:	INTERVAL STATUS
					IN.	TERVAL C (As sho	wn in item #26)		<del></del>		
DATE FIRST PR	RODUCED:	TEST DA	TE:		HOURS TESTE	D:	TEST PRODUCTIO RATES: →	N OIL-BBL:	GAS - MCF:	WATER BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS	S. CSG. PRI	ESS. API GR	AVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS
					IN.	TERVAL D (As sho	wn in item #26)			<del></del>	
DATE FIRST PR	RODUCED:	TEST DA	TE:		HOURS TESTE	D:	TEST PRODUCTIO RATES: →	N OIL BBL:	GAS - MCF:	WATER - 8BL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS	S. CSG. PRI	ESS. API GR	AVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS
32. DISPOSITIO	ON OF GAS (S	old, Used for F	uel, Vented, Etc	:.)		<u> </u>	· · · · · · · · · · · · · · · · · · ·		<del>gargarang padipasan ana ara-ara-ara-ara-ara-ara-ara-ara-ara-ar</del>	······································	
33. SUMMARY	OF POROUS 2	ZONES (Include	e Aquifers):					34. FORMATIO	ON (Log) MARKERS:	<del></del>	
	ant zones of po	rosity and conte	ents thereof: Con			m tests, including de	epth interval				
Formati	on	Top (MD)	Bottom (MD)		Descri	ptions, Contents, etc	<b>5</b> .		Name		Top (Measured Depth)
								GREEN BIRD'S N MAHOGA WASATO MESAVE	NEST ANY CH		1,271 1,582 1,945 4,422 6,570
	1										

35. ADDITIONAL REMARKS (Include plugging procedure)

The first 210' of the surface hole was drilled with a 12 ¼" bit. The remainder of surface hole was drilled with an 11" bit. DQX csg was run from surface to 4986'; LTC csg was run from 4986' to 8850'. Attached is the chronological well history, perforation report & final survey.

									_
36.	I hereby certif	ly that the foregoin	g and attached inf	formation is co	omplete and o	correct as dete	rmined from al	l available record	ÌS.

NAME (PLEASE PRINT) CARA MAHLER

TITLE RE
SIGNATURE

DATE

REGULATORY ANALYST

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- · drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\*\* ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to:

Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210

Box 145801

Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

<sup>\*</sup> ITEM 20: Show the number of completions if production is measured separately from two or more formations.

### **Operation Summary Report**

Well: NBU 922-36B1CS YELLOW Spud Date: 1/18/2012 Project: UTAH-UINTAH Site: NBU 922-36B PAD Rig Name No: ENSIGN 138/138, CAPSTAR 310/310 Event: DRILLING End Date: 2/24/2012 Start Date: 11/21/2011

Active Datum: RKB @5,029.01ft (above Mean Sea

UWI: NW/NE/0/9/S/22/E/36/0/0/26/PM/N/674/E/0/2282/0/0

Level)		`		_				
Date		Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U MD From (ft)	Operation
1/17/2012	6:00	- 11:00	5.00	DRLSUR	01	С	Р	SKID TO NBU 922-36B1CS, WELL 3/4. WELD ON RISER
	11:00	- 13:00	2.00	DRLSUR	01	В	Р	WELD ON RISER. SLIP/CUT 37' DRILL LINE. HOOK UP BOUY LINE
	13:00	- 16:30	3.50	DRLSUR	22	0	S	TOOK KICK FROM PREVIOUS WELL, NBU 922-36A1CS. CEMENTER CALLED
	16:30	- 18:00	1.50	DRLSUR	13	Α	S	CEMENT NBU 922-36A1CS, CEMENT DOWN 1 INCH, 200 SACKS, NO RETURNS.
	18:00	- 20:00	2.00	DRLSUR	13	Α	S	WAIT ON CEMENT
	20:00	- 20:30	0.50	DRLSUR	13	Α	S	CEMENT DOWN 1" ON NBU 922-36A1CS, 125 SACKS. NO RETURNS. MORE CEMENT ON THE WAY
		- 22:30	2.00	DRLSUR	13	Α	P	WAIT ON CEMENT
	22:30	- 23:00	0.50	DRLSUR	13	Α	P	922-36A1CS, CEMENT DOWN 1" 200 SACKS, NO RETURNS
	23:00	- 0:00	1.00	DRLSUR	13	Α	S	WAIT ON CEMENT
1/18/2012	0:00	- 2:30	2.50	DRLSUR	13	Α	S	WAIT ON CEMENT NBU 922-36A1CS
	2:30	- 3:30	1.00	DRLSUR	13	Α	\$	200 SX CEMENT DOWN 1" NBU 922-36A1CS.
	3:30	- 6:00	2.50	DRLSUR	13	Α	S	WAIT ON CEMENT
	6:00	- 7:00	1.00	DRLSUR				225 SX CEMENT FOWN 1" NBU 922-36A1CS.CEMENT TO SURFACE
	7:00	- 11:00	4.00	DRLSUR	13	Α	S	WOC, PU SPARE MOTOR, ORIGINAL MOTOR FROZE UP
	11:00	- 15:30	4.50	DRLSUR	02	D	Р	SPUD, DRILL T/ 210'
	15:30	- 18:00	2.50	DRLSUR	06	Α	Р	CIRC, POOH LDDS, PU 11.00 BIT AND DIR TOOLS
	18:00	- 19:30	1.50	DRLSUR	06	Α	P	INSTALL ROT RUBBER, TIH
	19:30	- 0:00	4.50	DRLSUR	02	D	P	DRILL F/210' T/ 635'. WOB 20, RPM 45, ROT 60, ON/OFF 100/840. UP/DWN/ROT 65/60/63
1/19/2012	0:00	- 11:30	11.50	DRLSUR	02	D	Р	DRILL F/ 635' T/ 1686'
	11:30	- 12:00	0.50	DRLSUR	07	Α	P	RIG SERVICE
	12:00	- 0:00	12.00	DRLSUR	02	D	Р	DRILL F/ 1686' T/ 2310', WOB 20, RPM 45, ON/OFF BTM 1030/900, UP/DWN/ROT 102/96/90. DRILLING AHEAD ON 1 AIR COMPRESSOR. MECHANIC ON SITE
1/20/2012	0:00	- 6:30	6.50	DRLSUR	0,2	D	P	DRILL F/ 2310' T/ 2560', TD, ON 1 AIR COMPRESSOR AT A REDUCED P RATE. MACHANIC ON ROUTE TO FIX DOWN COMPRESSOR WOB 20, RPM 45, ON/OFF BTM 1100/920, UP/DWN/ROT 115/93/108
	6:30	- 8:30	2.00	DRLSUR	05	С	Р	CIRC PRIOR TO POOH
	8:30	- 13:00	4.50	DRLSUR	06	D	Р	POOH, LDDS AND DIR TOOLS
	13:00	- 17:00	4.00	DRLSUR	12	С	Р	RUN 57 JTS 8 5/8, 28# CSNG. LAND CSNG SHOE SET @ 2517', BAFFLE SET @ 2470'
	17:00	- 17:30	0.50	DRLSUR	12	В	P	HOLD SAFETY MEETING, RUN 200' OF 1". RIG UP CEMENT TRUCK, 2" HARD LINES,. CEMENT HEAD, LOAD PLUG.
	17:30	- 18:00	0.50	DRLSUR	12	Ε	Р	CEMENTING, 300 SX INITIAL, 15.8 #
		- 19:30	1.50	DRLSUR	12	E	P	CEMENT DOWN BACKSIDE, 150 SX
		- 21:30	2.00	DRLSUR	13	A	' P	WOC
	18.50	- 21:30	2.00	DALOUK	10	^	F	VVQ

# **Operation Summary Report**

 Well: NBU 922-36B1CS YELLOW
 Spud Date: 1/18/2012

 Project: UTAH-UINTAH
 Site: NBU 922-36B PAD
 Rig Name No: ENSIGN 138/138, CAPSTAR 310/310

 Event: DRILLING
 Start Date: 11/21/2011
 End Date: 2/24/2012

Active Datum: RKB @5,029.01ft (above Mean Sea

UWI: NW/NE/0/9/S/22/E/36/0/0/26/PM/N/674/E/0/2282/0/0

Active Datum: F .evel)	1.5 (50,0			•				-MINO14/E/0/2282/0/0
Date		Time	Duration	Phase	Code	Sub	P/U MD	From Operation
	St	art-End	(hr)			Code	(1	rt)
	21:30	- 22:00	0.50	DRLSUR	12	E	Р	CEMENT DOWN BACKSIDE, 100 SX
	22:00	- 23:30	1.50	DRLSUR	13	Α	P	WOC
	23:30	- 0:00	0.50	DRLSUR	12	Ε	Р	CEMENT DOWN BACKSIDE, 125 SX
2/18/2012	21:00	- 22:00	1.00	MIRU	01	С	Р	SKID THE RIG OVER THE HOLE AND CENTER IT UP.
	22:00	- 22:30	0.50	MIRU	14	Α	P	NIPPLE UP THE BOP AND CHOKE
	22:30	- 23:00	0.50	MIRU	01	В	Р	FINISH RIGGING UP THE FLARE LINE, FLOW LINE, AND PANIC LINE
	23:00	- 0:00	1.00	MIRU	15	Α	Р	HELD A SAFTEY MEETING WITH A-1 TESTERS, RIGGED UP A-1 AND BEGAN TESTING THE BOP.
2/19/2012	0:00	- 3:30	3.50	MIRU	15	A	P ·	TEST FLOOR VALVES, TOP DRIVE VALVE, INSIDE & OUT SIDE KILL LINE & CHOKE LINE VALVES, HCR VALVE, CHOKE MANIFOLD, PIPE RAMS ,BLIND RAMS TO 250 PSI F/ 5 MIN, 5000 PSI F/ 10 MIN, ANNULAR TO 250 F/ 5 MIN, 2500 F/ 10 MIN, CASING TO 1500 PSI F/ 30 MIN, R/D TESTER
	3:30	- 6:30	3.00	MAINT	09	Α	Р	CUT AND SLIPPED 280' OF DRILLING LINE
	6:30	- 7:00	0.50	PRPSPD	14	В	Р	INSTALLED THE WEAR BUSHING
	7:00	- 9:00	2.00	DRLPRO	06	Α	Р	PICKED UP A BIT AND NEW MUD MOTOR, SCRIBED THE ASSEMBLY. TRIPPED IN THE HOLE WITH THE HEAVY WEIGHT DRILL PIPE.
	9:00	- 9:30	0.50	MAINT	07	Α	Р	RIG SERVICE
	9:30	- 10:00	0.50	MAINT	07	В	Р	LEVEL THE RIG
	10:00	- 11:30	1.50	DRLPRO	06	Α	Р	FINISH TRIPPING IN THE HOLE. TAGGED CEMENT @ 2420'
	11:30	- 12:30	1.00	DRLPRO	02	F	Р	DRILLED THE CEMENT AND FLOAT EQUIPMENT. 80 STKS. 360GPM RPM 100/40 WEIGHT ON BIT 12K
	12:30	- 0:00	11.50	DRLPRO	02	D	P	DRILL 2565' - 4561' , 1996' @ 173.6' HR , WOB 18-20, SPM 120, GPM 540 RPM 50/151,
								WATER 8.5 WT.  TRQ ON/OFF 10/8  PSI ON/OFF , 2030/1670  PU/SO/ROT 117/110/114  SLIDE 166', 2.33 @ 71.2'/HR  ROTATE 1830 ', 9.17 /HR @ 199.6 '/HR.  NOV RUNNING: DEWATERING  BIT POSITION 16.2'N & 14'E OF CENTER
2/20/2012	0:00	- 10:00	10.00	DRLPRO	02	D	P	DRILL 4561'- 6132', 1571' @ 157.1'/HR, WOB 18-20, SPM 120, GPM 540 RPM 50/151, WATER 8.5 WT. GEL SWEEPS TORQUE ON/OFF 10/8 PSI ON/OFF, 2245/1830 PU/SO/ROT 150/132/140 SLIDE 65', 1.08 HR. @ 60.2'/HR ROTATE .1506', 8.92 HR. @ 168.8'/HR NOV RUNNING: DEWATERING
								BIT POSITION: 10.07'N & 1.98' E OF CENTER
	10:00	- 10:30	0.50	MAINT	07	Α	Р	RIG SERVICE

6/5/2012 2:19:19PM

			1	Opera	tion S	Summary	Report	
Vell: NBU 922	-36B1CS YELLOW					Sp	ud Date: 1/18/2012	
Project: UTAH-	UINTAH		Site: NBU	922-36B	PAD		Rig Name No: ENSIGN 138/138, CAPSTAR 310/310	
vent: DRILLIN	IG		Start Date	e: 11/21/2	011		End Date: 2/24/2012	
Active Datum: I Level)	RKB @5,029.01ft (al	oove Mean Sea	1	UWI: N\	W/NE/0/9	NE/0/9/S/22/E/36/0/0/26/PM/N/674/E/0/2282/0/0		
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (ft)	
	10:30 - 18:00	7.50	DRLPRO	02	D	Р	DRILL 6132'- 6825' , 693' @ 92.4'/ HR ,	
	18:00 - 0:00	6.00	DRLPRO	02	D	P	WOB 18-20, SPM 120, GPM 540 RPM 50/151, WATER 8.5 WT. GEL SWEEPS WITH LCM TORQUE ON/OFF 11/9 PSI ON/OFF , 2240/1755 PU/SO/ROT 164/142/154 SLIDE: 38', .66 HR. @ 57.6'/HR ROTATE: 655', 6.84 HR. @ 95.8'/HR. NOV RUNNING: DEWATERING BIT POSITION: 15.75'N & .89'W OF CENTER DRILL 6825'- 7274', 449' @ 74.8'/ HR.	
	18:00 - 0:00	6.00	DRLPRO	02	D	۲	DRILL 6825'- 7274', 449' @ 74.8'/ HR, WOB 18-20, SPM 110, GPM 496 RPM 50/139, WATER 8.5 WT. TORQUE ON/OFF 11/10 PSI ON/OFF, 2775 / 2280 PU/SO/ROT 174/150/162 SLIDE: 28', 1.5 HR. @ 22'/HR ROTATE: 421', 4.5 HR. @ 93.5'/HR. NOV RUNNING: CONVENTIONAL 1 CENTRIFUGE RUNNING @ 30% - 30% OF THE TIME BIT POSITION: 15.86'N & 2.7'E OF CENTER NO FLARE MINIMAL SEEPING DISPLACED THE WATER WITH MUD @ 7000' MUD WT/10.5 VIS/34 LCM AT 15 MINUTES PER SACK DURING FLUID TRANSFER	
2/21/2012	0:00 - 13:30	13.50	DRLPRO	02	D	<b>P</b> *	DRILL 7274' - 8120', 846' @ 62.7'/ HR, WOB 18-20, SPM 110, GPM 496 RPM 50/139, MUD WT/10.5 VIS/34 TORQUE ON/OFF 11/10 PSI ON/OFF, 2775 / 2280 PU/SO/ROT 182/162/172 SLIDE: 37', 1.59 HR. @ 23.3'/HR ROTATE: 809', 11.91 HR. @ 67.9'/HR. NOV RUNNING: CONVENTIONAL 1 CENTRIFUGE RUNNING @ 30% - 30% OF THE TIME BIT POSITION: 11.73' N & 2.7' E OF CENTER NO FLARE MINIMAL SEEPING RAISED THE MW TO 11.5 @ 8000' RUNNING 1 SACK OF SAWDUST EVERY 10 MINUTES	
	13:30 - 14:00	0.50	DRLPRO	07	Α	Р	RIG SERVICE	

6/5/2012 2:19:19PM

3

### **Operation Summary Report**

 Well: NBU 922-36B1CS YELLOW
 Spud Date: 1/18/2012

 Project: UTAH-UINTAH
 Site: NBU 922-36B PAD
 Rig Name No: ENSIGN 138/138, CAPSTAR 310/310

 Event: DRILLING
 Start Date: 11/21/2011
 End Date: 2/24/2012

Active Datum: RKB @5,029.01ft (above Mean Sea

UWI: NW/NE/0/9/S/22/E/36/0/0/26/PM/N/674/E/0/2282/0/0

Level)		20.0 11. (0.20	Line and the second second				Once of the Assessment	
Date	1 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (ft)
	100000000000000000000000000000000000000	- 0:00	10.00	DRLPRO	02	D	P	DRILL 8120' - 8534' , 414' @ 41.4'/ HR , WOB 18-20, SPM 100, GPM 450 RPM 50/126, MUD WT/11.7 VIS/40 TORQUE ON/OFF 11/10 PSI ON/OFF , 2800 / 2250 PU/SO/ROT 187/170/176 SLIDE: 30', 1.75 HR. @ 17.1'/HR ROTATE: 384', 8.25 HR. @ 46.5'/HR. NOV RUNNING: CONVENTIONAL 1 CENTRIFUGE RUNNING @ 30% - 30% OF THE TIME BIT POSITION: 2.30' N & .55' W OF CENTER NO FLARE
2/22/2012	0:00	- 7:00	7.00	DRLPRO	02	D	P	LOST APP. 60 BBL. OF MUD  DRILL 8534'- 8873', 339' @ 48.4'/ HR,  WOB 18-20,
								SPM 100, GPM 450 RPM 50/126, MUD WT/11.7 VIS/40 TORQUE ON/OFF 11/10 PSI ON/OFF , 2800 / 2250 PU/SO/ROT 187/170/176 SLIDE: 0 ROTATE: 339', 7 HR. @ 48.4'/HR. NOV RUNNING: CONVENTIONAL 1 CENTRIFUGE RUNNING @ 30% - 30% OF THE TIME BIT POSITION: 6.99'S & 3.66 E OF CENTER NO FLARE
	7:00	- 8:30	1.50	DRLPRO	05	С	P	LOST APP. 90 BBL. OF MUD CIRCULATE AND CONDITION PRIOR TO TO THE WIPER TRIP. MW/11.7, 42/ VIS
	8:30	- 18:30	10.00	DRLPRO	06	E	<b>P</b>	WE MADE A WIPER TRIP TO THE CASING SHOE. TIGHT SPOTS @ 4280-4350' ON THE TRIP OUT. FILLED PIPE AT THE CASING SHOE AND 5000' ON THE WAY IN.
	18:30	- 20:30	2.00	DRLPRO	05	С	P	CIRCULATED AND CONDITIONED FOR LOGS
	20:30	- 0:00	3.50	DRLPRO	06 -	В	P	TRIP OUT OF THE HOLE FOR LOGS.
2/23/2012	0:00	- 2:30	2.50	DRLPRO	06	В	Р	TRIP OUT OF THE HOLE FOR LOGS. NO TIGHT SPOTS ON THE WAY OUT.
	2:30	- 3:00	0.50	DRLPRO	14	В	Р	PULLED THE WEAR BUSHING
	3:00	- 9:30	6.50	EVALPR	11	D	Р	HELD A SAFETY MEETING WITH BAKER ATLAS, RIGGED UP AND RAN TRIPLE COMBO LOGS. DRILLERS TD 8873', LOGGERS TD 8860'. RIGGED DOWN THE LOGGING TOOLS AND EQUIPMENT.
	9:30	- 20:00	10.50	CSG	12	С	P	HELD A SAFETY MEETING WITH FRANKS WESTATE AND RIGGED TO RUN CASING. RAN 211 TOTAL JOINTS, (92 JTS. OF 4.5"/I-80 / 11.6# / LTC), (119 JTS. OF 4.5" / 11.6# / I-80 / DQX). LANDED AT 8849.47, FLOAT COLLAR @ 8802.23, MV MARKER @ 6504.21, DQX CROSS OVER @ 4967.76. FILLED THE PIPE @ 135', 854', 2767', & 5060'
	20:00	- 21:00	1.00	CSG	05	D	Р	CIRCULATED THE CASING @ 80 STOKES, 360 GPM 850 PSI. WE HAD A 10' FLARE ON BOTTOMS UP WITH 11.7 MUD WEIGHT.

				U	S ROC	KIES RI	EGION			
				Opera	ition S	Summa	ıry Report			
Well: NBU 922	2-36B1CS YELLOW						Spud Date: 1/18	W2012		
Project: UTAH	-UINTAH		Site: NBI	J 922-36E	PAD			Rig Name No: ENSIGN 138/138, CAPSTAR 310/310		
Event: DRILLII	Start Dat	e: 11/21/2	2011			End Date: 2/24/2012				
Active Datum: Level)		UWI: N	W/NE/0/9	)/S/22/E/3	WE/0/2282/0/0					
Date	Time	Duration	Phase	Code	Sub	P/U	MD From	Operation		
	Start-End	(hr)			Code		(ft)			
	21:00 - 0:00	3.00	CSG	12	E	Р		DROPPED BOTTOM PLUG, PUMPED 25 BBL 8.34		
								WATER SPACER, 480 SX PREMIUM LITE II CEMENT		
								+ 0.5 LBS/SX STATIC FREE + 0.4% BWOC R-3 +		
								0.25 LBS/SX CELLO FLAKE + 5 LBS/SX KOL SEAL +		
								0.2% BWOC SODIUM METASILICATE + 8% BWOC		
								BENTONITE II +.4 BWOC FL-52 + 101.8% FRESH		
								WATER 12.5#, 2.02 YIELD LEAD CEMENT , 1295 SX 50:50 POZ ( ASH FLY ) CLASS G + 0.005 LBS/SX		
								STATIC FREE + 10% BWOW SODIUM CHLORIDE +		
								0.15% BWOC R-3 + 0.002 GPS FP-6L + 2%		
								BENTONITE II + 58.7% FRESH WATER, DROPPED		
								THE TOP PLUG, DISPLACE W/ 136.9 BBLS		
								CLAYCARE + 1 GAL MAGNACIDE @ 8.34 PPG		
								WATER , FINAL LIFT 2703 PSI, BUMPED BLUG @		
								3304 PSI , FLOATS HELD, 25 BBLS CEMENT BACK		
								TO PIT , TOP OF TAIL EST @ 3800 ' , FLUSH STACK,		

R/D CEMENTERS

RELEASED @ 03:00

THE SLIPS

RIGGED DOWN BJ SERVICES

SET THE SLIPS THROUGH THE STACK WITH 90K ON

NIPPLE DOWN AND CUT THE CASING OFF

PREPPED THE RIG TO SKID THE RIG WAS

6/5/2012 2:19:19PM

2/24/2012

0:00 - 0:30

0:30 - 1:00

1:00 - 2:30

2:30 - 3:00

0.50

0.50

1.50

0.50

CSG

CSG

MIRU

MIRU

12

14

14

01

В

В

Α

Ε

Р

P

Р

#### 1 General

#### 1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

#### 1.2 Well/Wellbore Information

Well	NBU 922-36B1CS YELLOW	Wellbore No.	ОН	
Well Name	NBU 922-36B1CS	Wellbore Name	NBU 922-36B1CS	
Report No.	1	Report Date	4/4/2012	
Project	UTAH-UINTAH	Site	NBU 922-36B PAD	
Rig Name/No.		Event	COMPLETION	
Start Date	4/19/2012	End Date	4/24/2012	
Spud Date	1/18/2012	Active Datum	RKB @5,029.00usft (above Mean Sea Level)	
UWI	NW/NE/0/9/S/22/E/36/0/0/26/PM/N/674/E/0/2282	/0/0		

#### 1.3 General

Contractor		Job Method	PERFORATE	Supervisor	
Perforated Assembly	PRODUCTION CASING	Conveyed Method	WIRELINE		

#### 1.4 Initial Conditions

#### 1.5 Summary

Fluid Type	KCL WATER	Fluid Density	Gross Interval	5,994.0 (usft)-8,785.0 (usft	Start Date/Time	4/9/2012 12:00AM
Surface Press		Estimate Res Press	No. of Intervals	42	End Date/Time	4/9/2012 12:00AM
TVD Fluid Top		Fluid Head	Total Shots	213	Net Perforation Interval	71.00 (usft)
Hydrostatic Press		Press Difference	Avg Shot Density	3.00 (shot/ft)	Final Surface Pressure	
Balance Cond	NEUTRAL				Final Press Date	

#### 2 Intervals

#### 2.1 Perforated Interval

Date	Formation/ Reservoir	(usft)	CCL-T MD To	AND AND EAST OF A POPULATION OF	\$250 DOS - PHONOS CONTROL	Misfires/ Diamete Carr Type /C Add. Shot r (in)	arr Manuf. Carr Size (in)	Phasing (°)	Charge Desc / Charge Charge Manufacturer Weight (gram)
4/9/2012	WASATCH/		5,99	4.0 6,000.0	3.00	0.360 EXP/	3.375	120.00	23.00 PRODUCTIO
12:00AM									N N

#### 2.1 Perforated Interval (Continued)

Date	Formation/	CCL@	CCL-T	MD Top	MD Base	Shot	Misfires/	Diamete	Carr Type /Carr Manuf	Carr	Phasing	Charge Desc/Charge	Charge	Reason	Misrun
	Reservoir	(usft)	S (usft)	(usft)	(usft)	Density (shot/ft)	Add. Shot	r (in)	1900 - 1975 1900 - 1975 1900 - 1975	Size (in)	(*)	Manufacturer	Weight (gram)		
4/9/2012	MESAVERDE/		Lagra	6,584.0	6,585.0			0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
12:00AM 4/9/2012	MESAVERDE/		! !	6,632.0	6,633.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO	
12:00AM 4/9/2012	MESAVERDE/			6 6E40	6,655.0	3.00		0.360	EYD!	3.375	120.00			N PRODUCTIO	
12:00AM	WESAVERDE/	: :		6,654.0	6,655.0	3.00		0.360		3.373				N	
4/9/2012 12:00AM	MESAVERDE/	4		6,690.0	6,692.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			6,724.0	6,726.0	3.00		0.360	EXP/	3.375	120.00	:		PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		:	6,740.0	6,741.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			6,788.0	6,790.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			6,820.0	6,821.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		!	6,882.0	6,884.0	3.00		0.360	EXP/	3.375	120.00		1	PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/	· · · · · · · · · · · · · · · · · · ·	i	6,948.0	6,950.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			6,996.0	6,997.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			7,062.0	7,064.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			7,096.0	7,097.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			7,170.0	7,171.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			7,212.0	7,213.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			7,234.0	7,235.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			7,284.0	7,286.0	3.00		0.360	EXP/	3.375	120.00	T	1	PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		i	7,416.0	7,417.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/	- 4		7,432.0	7,433.0	3.00		0.360	EXP	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			7,510.0	7,511.0	3.00		0.360	EXP/	3.375	120.00			PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/			7,590.0	7,592.0	3.00		0.360	EXP	3.375	120.00			PRODUCTIO N	

### 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T MD Top S (usft)	MD Base (usft)	Shot Density	Misfires/ Diamete Add. Shot r	Carr Type /Carr Manuf	Carr Size	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Reason Weight	Misrun
	Reservoir	(usit)	(usft)	(usit)	(shot/ft)	Add, SHOL   (in)		(in)	· · · · · · · · · · · · · · · · · · ·	Waliulaciulei	(gram)	
4/9/2012 12:00AM	MESAVERDE/		7,664.0	7,667.0	3.00	The state of the s	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		7,725.0	7,726.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		7,752.0	7,753.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		7,790.0	7,792.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		7,880.0	7,881.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		7,910.0	7,913.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,050.0	8,053.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	i
4/9/2012 12:00AM	MESAVERDE/		8,123.0	8,126.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,148.0	8,150.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	!
4/9/2012 12:00AM	MESAVERDE/		8,198.0	8,200.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,236.0	8,237.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,274.0	8,275.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/	:	8,324.0	8,325.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,344.0	8,348.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/	:	8,542.0	8,544.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,552.0	8,553.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,752.0	8,754.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,761.0	8,762.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,778.0	8,779.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	
4/9/2012 12:00AM	MESAVERDE/		8,784.0	8,785.0	3.00	0.360	EXP/	3.375	120.00		23.00 PRODUCTIO N	

#### 3 Plots

					Upera	tion S	ummary	Keport
/ell: NBU 922-	36B1CS \	ELLOW					s	oud Date: 1/18/2012
Project: UTAH-l	JINTAH			Site: NBU	J 922-36B	PAD		Rig Name No: ROYAL WELL SERVICE 2/2, SWABBCO 6/6
vent: COMPLETION Start D					e: 4/19/20	12		End Date: 4/24/2012
Active Datum: RKB @5,029.01ft (above Mean Sea .evel)				UWI: N\	N/NE/0/9	/\$/22/E/36/0/	0/26/PM/N/674/E/0/2282/0/0	
Date	and the second second	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (ft)
3/30/2012	6:45	- 7:00	0.25	COMP	48		P	HSM & JSA W/ROYAL WELL SERVICE
	7:00	- 17:00	10.00	COMP	30	Α	P	ROAD RIG FROM NBU 921-24AT TO LOC. MIRU - SPOT EQUIP. WHP 0 PSI. NDWH, NU BOPS. R/U FLOOR & TBG EQUIP. PREP & TALLY TBG. PU 3 7/8" BIT & SUB. RIH ON 278 JTS 2 3/8" TBG. TAG FLOAT COLLAR @ 8835'. CIRC WELL CLEAN W/80 BBLS TMAC. (DIRTY CMT WATER RETURNED). POOH & L/D TBG & BHA. ND BOPS, NUWH. SWI - RDMOL. SDFWE.
3/31/2012								
4/4/2012	10:00	- 11:30	1.50	COMP	33		P	FILL SURFACE CSG. MIRU B&C QUICK TEST. PSI TEST T/ 1000 PSI. HELD FOR 15 MIN LOST 05 PSI. PSI TEST T/ 3500 PSI. HELD FOR 15 MIN LOST 38 PSI. 1ST PSI TEST T/ 7000 PSI. HELD FOR 30 MIN LOST 48 PSI. NO COMMUNICATION OR MIGRATION WITH SURFACE CSG
								BLEED OFF PSI, MOVE T/ NEXT WELL. SWIFW
4/5/2012	8:00	- 12:00	4.00	COMP	37	В	Р	HSM, MOVING R/U P/U RIH W/ 3-1/8 EXPEND, 23 GRM, 0.36" HOLE, PERF MESAVERDE AS PER SAY IN DESIGN SWIFN
4/9/2012	6:00	- 10:30	4.50	COMP	48		Р	HSM, PINCH POINTS, MIRU PRESSURE TEST SURFACE LINES TO 8,500#, OPEN WELL

					U	S ROC	KIES R	EGION	
			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		Opera	tion S	Summa	ary Report	
Well: NBU 922-3	6B1CS YE	ELLOW		253 8 727 S ROBERTS	1.000.10.02.00	A STATE OF THE STA		Spud Date: 1/18	/2012
Project: UTAH-U	INTAH			Site: NBU	J 922-36B	PAD			Rig Name No: ROYAL WELL SERVICE 2/2, SWABBCO 6/6
Event: COMPLE	TION			Start Date	e: 4/19/20	12			End Date: 4/24/2012
Active Datum: Rh	(B @5,029	9.01ft (abov	e Mean Sea		UWI: NV	<b>V/NE</b> /0/9	/S/22/E/3	6/0/0/26/PM/N/674	/E/0/2282/0 <b>/</b> 0
Level)						CONTRACTOR WITHOUT A			
Date	Star	ime rt-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	10:30	- 17:00	6.50	COMP	36	В	Р		PERF & FRAC FOLLOWING WELL AS PER DESIGN W/ 30/50 MESH SAND & SLK WTR. ALL CBP'S ARE HALIBURTON 8K CBP'S. REFER TO STIM PJR FOR FLIUD, SAND AND
									CHEMICL VOLUME PUM'D  FRAC STG #1] WHP=1,580#, BRK DN  PERFS=3,581#, @=4.7 BPM, INJ RT=48.2, INJ  PSI=5,683#, INITIAL ISIP=2,433#, INITIAL FG=.72,  FINAL ISIP=2,551#, FINAL FG=.73, AVERAGE  RATE=49.3, AVERAGE PRESSURE=4,875#, MAX  RATE=51.7, MAX PRESSURE=6,061#, NET  PRESSURE INCREASE=118#, 19/24 CALC PERFS  OPEN. X OVER TO WIRE LINE  PERF STG #2] P/U RIH W/ HALIBURTON 8K CBP &  PERF GUN, SET CBP @=8,378', PERF MESAVERDE  USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS  PERSAY IN PROCEDURE, X OVER TO FRAC CREW  FRAC STG #2] WHP=980#, BRK DN PERFS=2,481#,  @=3.8 BPM, INJ RT=50.9, INJ PSI=4,455#, INITIAL  ISIP=1,539#, INITIAL FG=.62, FINAL ISIP=2,539#,  FINAL FG=.75, AVERAGE RATE=50.8, AVERAGE  PRESSURE=4,489#, MAX RATE=51, MAX  PRESSURE=5,367#, NET PRESSURE  INCREASE=1,000#, 23/27 85% CALC PERFS OPEN.  X OVER TO WIRE LINE
									PERF STG #3] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=8,180', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW
									FRAC STG #3] WHP=1,880#, BRK DN PERFS=5,575#, @=4.7 BPM, INJ RT=50.5, INJ PSI=4,922#, INITIAL ISIP=2,324#, INITIAL FG=.73, FINAL ISIP=2,250#, FINAL FG=.72, AVERAGE RATE=50.7, AVERAGE PRESSURE=4,650#, MAX RATE=51.1, MAX PRESSURE=5,575#, NET PRESSURE INCREASE=-74#, 24/24 100% CALC PERFS OPEN. X OVER TO WIRE LINE
4/10/2012	6:30	- 6:45	0.25	СОМР	48		P		PERF STG #4] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=7,943', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW SWIFN HSM, SLIPS / TRIPS & FALLS

6/5/2012 2:30:18PM

2

/ell: NBU 922-36B1CS YELLOW		ate: 1/18/2012				
roject: UTAH-UINTAH	Site: NBU 922-36B PAD	Rig Name No: ROYAL WELL SERVICE 2/2,				
		SWABBCO 6/6				
ent: COMPLETION	Start Date: 4/19/2012	End Date: 4/24/2012				
tive Datum: RKB @5,029.01ft (above Mean Sea	UWI: NW/NE/0/9/S/22/E/36/0	/0/26/PM/N/674/E/0/2282/0/0				
/el)  Date Time Duration	Phase Code Sub P/U	MD From Operation				
Start-End (hr)	Code	(ft)				
6:45 - 16:30 9.75	COMP 36 B P	FRAC STG #4] WHP=1,710#, BRK DN				
		PERFS=3,212#, @=4.1 BPM, INJ RT=50, INJ				
		PSI=3,978#, INITIAL ISIP=2,214#, INITIAL FG=.72,				
		FINAL ISIP=3,000#, FINAL FG=.69, AVERAGE				
		RATE=50, AVERAGE PRESSURE=3,956#, MAX				
		RATE=50.3, MAX PRESSURE=4,662#, NET				
		PRESSURE INCREASE=-241#, 24/24 100% CALC PERFS OPEN. X OVER TO WIRE LINE				
		PERF STG #5] P/U RIH W/ HALIBURTON 8K CBP &				
		PERF GUN, SET CBP @=7,697', PERF MESAVERDE				
		USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW				
		FRAC STG #5] WHP=1,550#, BRK DN				
		PERFS=2,796#, @=4.5 BPM, INJ RT=51, INJ				
		PSI=4,118#, INITIAL ISIP=1,852#, INITIAL FG=.68,				
		FINAL ISIP=2,068#, FINAL FG=.71, AVERAGE				
		RATE=50.8, AVERAGE PRESSURE=4,144#, MAX				
		RATE=50.9, MAX PRESSURE=4,873#, NET				
		PRESSURE INCREASE=216#, 24/24 100% CALC				
		PERFS OPEN. X OVER TO WIRE LINE				
		PERF STG #6] P/U RIH W/ HALIBURTON 8K CBP &				
		PERF GUN, SET CBP @=7,316', PERF MESAVERDE				
		USING 3-1/8 EXPEND, 2RM, 0.36" HOLE. AS				
		PERSAY IN PROCEDURE, X OVER TO FRAC CREW				
		FRAC STG #6] WHP=1,630#, BRK DN				
		PERFS=4,023#, @=4.7 BPM, INJ RT=50.8, INJ				
		PSI=4,047#, INITIAL ISIP=1,500#, INITIAL FG=.69,				
		FINAL ISIP=2,128#, FINAL FG=.74, AVERAGE				
		RATE=50.8, AVERAGE PRESSURE=3,956#, MAX				
		RATE=51.2, MAX PRESSURE=4,836#, NET				
		PRESSURE INCREASE=628#, 24/24 100% CALC				
		PERFS OPEN. X OVER TO WIRE LINE				
		PERF STG #7] P/U RIH W/ HALIBURTON 8K CBP &				
		PERF GUN, SET CBP @=7,027', PERF MESAVERDE				
		USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS				
		PERSAY IN PROCEDURE, X OVER TO FRAC CREW				
		FRAC STG #7] WHP=315#, BRK DN PERFS=1,703#,				
		@=4.7 BPM, INJ RT=50.9, INJ PSI=3,682#, INITIAL				
		ISIP=10,43#, INITIAL FG=.59, FINAL ISIP=1,957#,				
		FINAL FG=.72, AVERAGE RATE=50.9, AVERAGE				
		PRESSURE=3,748#, MAX RATE=51.2, MAX				
		PRESSURE=4,381#, NET PRESSURE				
		INCREASE=914#, 23/24 97% CALC PERFS OPEN. X OVER TO WIRE LINE				
		PERF STG #8] P/U RIH W/ HALIBURTON 8K CBP &				
		DEDE OUR OFF ORD A 4774 DEDE MEAN TERE				
		PERF GUN, SET CBP @=6,771', PERF MESAVERDE				
		PERF GUN, SET CBP @=6,771', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW				

# **Operation Summary Report**

Well: NBU 922-3	B6B1CS Y	ELLOW						Spud Date: 1/18/2012
Project: UTAH-L	JINTAH			Site: NBI	J 922-36E	PAD		Rig Name No: ROYAL WELL SERVICE 2/2, SWABBCO 6/6
Event: COMPLE	TION			Start Dat	e: 4/19/20	12		End Date: 4/24/2012
Active Datum: R Level)	KB @5,0	29,01ft (abov	ve Mean Sea		UWI: N	W/NE/0/9	9/S/22/E/3	6/0/0/26/PM/N/674/E/0/2282/0/0
Date	4 5 5 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (ft)
4/11/2012	6:30	- 6:45	0.25	COMP	48		P	FRAC STG #8] WHP=126#, BRK DN PERFS=475#, @=4.7, INITIAL ISIP=230#, INITIAL FG=.47. X OVER TO WIRE LINE DID NOT FRAC ONLT BREAK DOWN, ZONE WENT ON A VACCUME. SWIFN HSM, R/D OVER HEAD LOADS
	6:45	- 9:00	2.25	COMP	36	В	P	PERF STG #9] P/U RIH W/ HALIBURTON 8K CBP & PERF GUN, SET CBP @=6,030', PERF MESAVERDE USING 3-1/8 EXPEND, 23 GRM, 0.36" HOLE. AS PERSAY IN PROCEDURE, X OVER TO FRAC CREW WELL WENT ON A VACCUME DID NOT BREAK DN OR FRAC, DID NOT SET A TOP KILL.
4/19/2012	7:00	- 7:15	0.25	COMP	48		Р	TOTAL FLUID PUMP'D=7,692 BBLS TOTAL SAND PUMP'D=152,099# JSA= TALLY TUBING
	7:15	- 17:00	9.75	COMP	30		P	TALLY & PU TUBING RIH TAG CBP @ 6026' PUH TO 5990' NU SUPERIOR EST INJ RATE 1/4 BBL/MIN @ 1800 PSI (NOT ENOUGH RATE TO SQUEEZE) RU CEM POOH PU 3-7/8" BIT TAG CBP @ 6026' EST REV CIRC DRILL THRU HALLI 8K CBP (NO SAND ABOVE PLG, LOST CIRC) CONTINUE TO RIH TAG @ 6758' POOH W/ BIT SIW SDFN
4/20/2012	7:00 7:15	- 7:15 - 15:00	0.25 7.75	COMP	48 30		P P	JSA= PUMPING CEM  SIWP=400 PSI PU NOTCHED COLLAR RIH W/ 208  JNTS EOT @ 6593' RU SUPERIOR TEST PUMP &  LINES PUMP 20 BBLS FRESH AHEAD INJ RT 3 BBLS  PER MIN @ 400# MIX & PUMP 100 SKS G CEM (20  BBLS SLURRY) @ 22 OF 25 BBLS DISP PSI @  1200# .3 BBLS PER MIN SD PUMP PUH 5 JNTS EOT  @ 6434' REV CIRC GET 2-1/2 BBLS CEM BACK CIRC  CLEAN POOH W/ TUBING APPLY 500# ON CSG SIW  SDFW
4/23/2012	7:00	- 7:15	0.25	COMP	48		Р	JSA= DRILLING CEMENT
	7:15	- 17:00	9.75	COMP	30		Р	SIWP=0 PSI PU 3-7/8" BIT & BS RIH TAG TOC @ 6462' RU PUMP EST REV CIRC DRILL THRU CEM TO 6751' CIRC CLEAN TEST SQUEEZE TO 1000# LOST 200# IN 3 MIN POOH W/ BIT PU POBS PKG RIH TAG @ 6751' CBP @ 6771' PREP TO D/O PLUGS IN AM
4/24/2012	7:00	- 7:15	0.25	COMP	48		P	JSA= OPERATING PUMP

		US ROCK	ES REGION	The second second second			
		Operation Su	mmary Report				
Vell: NBU 922-36B1CS YELLOW			Spud Date: 1/18	/2012			
roject: UTAH-UINTAH	Site: NB	BU 922-36B PAD		Rig Name No: ROYAL WELL SERVICE 2/2, SWABBCO 6/6			
vent: COMPLETION	Start Da	ate: 4/19/2012		End Date: 4/24/2012			
ctive Datum: RKB @5,029.01ft (above Mean Sea evel)		UWI: NW/NE/0/9/S	/22/E/36/0/0/26/PM/N/674	/0/0/26/PM/N/674/E/0/2282/0/0			
Date Time Duration Start-End (hr)	Phase	Code Sub-	P/U MD From (ft)	Operation			
7:15 - 17:00 9.75	COMP	30	P	SIWP= 0 PSI EST CIRC TEST BOPS DRILL THRU 1ST CBP			
				PLUG #1] DRILL THRU HALLI 8K CBP @ 6771' IN 11 MIN W/ 0 INCREASE (GOOD CIRC)			
				PLUG #2] CONTINUE TO RIH TAG SAND @ 6992' (35' FILL) C/O & DRILL THRU HALLI 8K CBP @ 7027' IN 7 MIN W/ 50# INCREASE			
				PLUG #3] CONTINUE TO RIH TAG SAND @ 7300' (16' FILL) C/O & DRILL THRU HALLI 8K CBP @ 7316' IN 7 MIN W/ 100# INCREASE			
				PLUG #4] CONTINUE TO RIH TAG SAND @ 7677' (20' FILL) C/O & DRILL THRU HALLI 8K CBP @ 7697' IN 7 MIN W/ 100# INCREASE			
				PLUG #5] CONTINUE TO RIH TAG SAND @ 7918' (25' FILL) C/O & DRILL THRU HALLI 8K CBP @ 7943' IN 5 MIN W/ 50# INCREASE			
				PLUG #6] CONTINUE TO RIH TAG SAND @ 8153' (25' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8180' IN 8 MIN W/ 0 INCREASE			
				PLUG #7] CONTINUE TO RIH TAG SAND @ 8348' (30' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8378' IN 5 MIN W/ 50# INCREASE			
				PBTD] CONTINUE TO RIH TAG SAND @ 8782' (20' FILL) C/O & DRILL TO PBTD @8802' CIRC CLEAN			
				PUH LD 21 JNTS LAND TUBING ON HNGR W 257 JNTS EOT @ 8163.33' RD DRILLING EQUIP, RD FLOOR & TUBING EQUIP ND BOPS NU WELLHEAD DROP BALL PUMP OFF BIT @2000# SIW NU & TEST FLOW LINE TURN WELL OVER TO FBC RD RIG MOVE TO NBU 922-36B RU RIG			
				TUBING DETAIL K.B14.00'			
				HANGER			
				EOT8163.33'			
				TOTAL FLUID PUMPED=7692 BBLS RIG REC= 2500 BBLS LEFT TO REC= 5192 BBLS			
				CTAP DEL= 283 JNTS			
				RIG USED= 257 JNTS			
				RETURNED= 26 JNTS			

	Operation Sum	imary Report
Well: NBU 922-36B1CS YELLOW		Spud Date: 1/18/2012
Project: UTAH-UINTAH	Site: NBU 922-36B PAD	Rig Name No: ROYAL WELL SERVICE 2/2, SWABBCO 6/6
Event: COMPLETION	Start Date: 4/19/2012	End Date: 4/24/2012
Active Datum: RKB @5,029.01ft (above Mean Sea Level)	UWI: NW/NE/0/9/S/22	2/E/36/0/0/26/PM/N/674/E/0/2282/0/0
Date Time Duration Start-End (hr)	Phase Code Sub Pr	U MD From Operation (ft)
7:00 -	50	WELL IP'D ON 4/25/2012 - 2041 MCFD, 0 BOPD, 580 BWPD, CP 2262#, FTP 1577#, CK 20/64, LP 98#, 24 HRS
4/26/2012 -		

6/5/2012

2:30:18PM

### 1 General

#### 1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

#### 1.2 Well Information

Well	NBU 922-36B1CS YELLOW	Wellbore No.	ОН
Well Name	NBU 922-36B1CS	Common Name	NBU 922-36B1CS
Project	UTAH-UINTAH	Site	NBU 922-36B PAD
Vertical Section		78.55 (°) North Reference	True
Azimuth			
Origin N/S		Origin E/W	
Spud Date	1/18/2012	UWI	NW/NE/0/9/S/22/E/36/0/0/26/PM/N/674/E/0/2282/ 0/0
Active Datum	RKB @5,029.01ft (above Mean Sea Level)		

# 2 Survey Name

### 2.1 Survey Name: Survey #1

Survey Name	Survey #1	Company	SCIENTIFIC DRILLING INTL
Started	1/19/2012	Ended	
Tool Name		Engineer	Anadarko Employee

### 2.1.1 Tie On Point

MD Inc (n) (°)	<b>Azi</b> (°)	TVD (ft)	N/S E/W (ft) (ft)	
	353.38			

#### 2.1.2 Survey Stations

Date	Туре	MD	Inc	Azi	TVD	N/S	EW	V. Sec	DLeg	Build	Turn	TFace
		(ft)	(9)	(9)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)	(*)
1/18/2012	NORMAL	169.00	0,35	353,38	169,00	0,50	-0.06	0.04	0.21	0.21	0.00	353,38
ng again ti at galante a na ata an an an tarante	NORMAL	257.00	0.44	28.09	257.00	1.06	0.07	0.28	0.29	0.10	39.44	87.33
a para paga paga maga an arawa	NORMAL	350.00	1.41	57.62	349.98	1.99	1.20	1.58	1,13	1.04	31.75	41.45
4-14-1-4-1-4-1-4-1-4-4-4-4-4-4-4-4-4-4-	NORMAL	439.00	2.42	74.37	438.93	3.08	3,94	4.47	1.29	1.13	18.82	37.54
A JOSEPH CONTRACTOR OF THE STREET, STR	NORMAL	533.00	4.13	75.73	532.78	4.45	9.13	9.83	1.82	1.82	1.45	3.28
and the second of	NORMAL	626.00	6.16	79.07	625.40	6,22	17.28	18.17	2.21	2.18	3.59	10.06
1/19/2012	Tie On	5.00	0.00	0.00	5.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
1/19/2012	NORMAL	720,00	7.30	75,47	718.75	8.68	28.01	29.18	1.29	1.21	-3.83	-22.10
yay ay a manadamin a ta a common of 9	NORMAL	815.00	8.53	76.43	812.84	11.85	40.70	42.24	1.30	1.29	1,01	6.61
na opinajneju na jakona ne elektri	NORMAL.	909.00	9.67	75.73	905.66	15.43	55.13	57.10	1.22	1.21	-0.74	-5.89
	NORMAL	1,003.00	10.64	74.15	998.19	19.74	71.13	73.63	1.07	1.03	-1.68	-16.80
	NORMAL	1,096.00	11.61	74.41	1,089.44	24.60	88.40	91.53	1.04	1.04	0.28	3.09
arran i en elimination com	NORMAL	1,188.00	12.13	74.32	1,179.47	29.70	106.63	110.40	0.57	0.57	-0.10	-2.08
	NORMAL.	1,283.00	12.75	73.80	1,272.24	35.33	126.30	130.80	0.66	0.65	-0.55	-10.50
man, zruga a migrzoru munici	NORMAL	1,377.00	13.06	75.56	1,363.87	40.87	146.55	151.75	0.53	0.33	1.87	52.60
	NORMAL	1,472.00	13.84	75.43	1,456.26	46.40	167.94	173.81	0.82	0.82	-0.14	-2.28
Charles and a second of the Co. Section	NORMAL	1,567.00	12.32	79.46	1,548.79	51.12	188.91	195.29	1.87	-1.60	4.24	150.99
ray o rayona ya rayon ini ini rayondany far by abay	NORMAL	1,663.00	11.61	78.10	1,642.71	54.98	208.43	215,19	0.80	-0.74	-1.42	-159.01
annone e como como esta	NORMAL	1,758.00	11.27	74.79	1,735.82	59.39	226.74	234.02	0.78	-0,36	-3.48	-118.99

### 2.1.2 Survey Stations (Continued)

Date	Type	MD	Inc	Azi	TVD	N/S	E/W	V. Sec	DLeg	Build	Turn	TFace
		(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)	(°)
1/19/2012	NORMAL	1,854.00	11.38	74.46	1,829.95	64.39	244.92	252.82	0.13	0.11	-0.34	-30.67
· Transcription Communication	NORMAL	1,946.00	10.50	73.03	1,920.28	69.27	261.68	270.22	1.00	-0.96	-1.55	-163.56
and the second of the second o	NORMAL	2,041.00	10.55	70.46 2,013	2,013.68	74.70	278.15	287.45	0.50	0.05	-2.71	-85.18
de de l'imperiològique e con l'Ampolita, le l'applit de l'Ampolita de l'Ampolita de l'Ampolita de l'Ampolita d	NORMAL	2,136.00	10.55	72.92	2,107.08	80.17	294.66	304.71	0.47	0.00	2.59	91.21
· · · · · · · · · · · · · · · · · · ·	NORMAL	2,229.00	10.90	74.59	2,198.45	85.00	311.28	321.96	0.50	0,38	1.80	42,43
1/20/2012	NORMAL	2,325.00	10.29	76.17	2,292.82	89.46	328.36	339.58	0.70	-0.64	1.65	155.31
Santan Caramana and Car	NORMAL	2,420.00	9.76	73.62	2,386.37	93.76	344.32	356.08	0.73	-0.56	-2,68	-141.30
	NORMAL	2,491.01	9.94	72.57	2,456.32	97.30	355.94	368.17	0.36	0.25	-1.48	-45.46

### 2.2 Survey Name: Survey #2

Survey Name	Survey #2	Company	SCIENTIFIC DRILLING INTL
Started	2/19/2012	Ended	
Tool Name	MWD	Engineer	DAN CHAMBLEE

### 2.2.1 Tie On Point

	MD (ft)	Inc. (°)	Azi (°)	TVD (ft)	N/S (ft)	EW (ft)
Г	2,491.01	9.94	72.57	2,456.32	97.30	355.94

#### 2.2.2 Survey Stations

Date	Туре	MD	Inc	Azi	TVD	N/S	E/W	V. Sec	DLeg	Build	Turn	TFace
		(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)	(*)
2/19/2012	Tie On	2,491.01	9.94	72.57	2,456.32	97.30	355.94	368.17	0.00	0.00	0.00	0.00
2/19/2012	NORMAL	2,577.01	9.81	74.10	2,541.05	101,53	370.07	382.86	0.34	-0.15	1.78	117.11
	NORMAL	2,672.01	9.47	77.36	2,634.71	105.45	385.48	398.74	0.68	-0.36	3.43	123.52
The Control of the Co	NORMAL	2,766.01	8.48	84.46	2,727.56	107.81	399,92	413.37	1.58	-1.05	7.55	135.26
Commence the section of the section of the	NORMAL	2,861.01	8.21	82.04	2,821.55	109.43	413.61	427.10	0.47	-0.28	-2.55	-128.74
Merchanism of the Penter	NORMAL	2,955.01	7.55	83.04	2,914.66	111.11	426.39	439,96	0.72	-0.70	1.06	168.76
es compression on the extension	NORMAL	3,050.01	6.39	76.80	3,008.96	113.07	437.73	451.47	1.46	-1.22	-6.57	-149.94
. Note as a serie of the contract	NORMAL	3,145.01	4.86	69.88	3,103.50	115.66	446.66	460.73	1.76	-1.61	-7.28	-159.51
****	NORMAL	3,239.01	3.06	63,60	3,197.27	118,15	452.64	467.09	1.97	-1.91	-6.68	-169.57
APRIL	NORMAL	3,334.01	1.27	72.61	3,292.20	119.59	455.92	470.59	1.91	-1.88	9.48	173.71
cal stars of the hope become the set	NORMAL	3,428.01	0.79	98.39	3,386.19	119.81	457.56	472.23	0.70	-0.51	27.43	148.41
	NORMAL	3,523.01	0.62	169.09	3,481.18	119.21	458.30	472.84	0.87	-0.18	74.42	134.99
and and and an artist of the section	NORMAL	3,617.01	0.83	182.62	3,575.18	118.03	458.37	472.67	0.29	0.22	14.39	46.08
	NORMAL	3,712.01	1.32	183.09	3,670.16	116.25	458,28	472,23	0.52	0.52	0.49	1.27
	NORMAL	3,806.01	0.53	185.76	3,764.15	114.73	458.17	471.83	0.84	-0.84	2.84	178.21
en a la about de la Estado de Santo	NORMAL	3,901.01	1.49	179.69	3,859.13	113.06	458.14	471.46	1.02	1.01	-6.39	-9.40
encountry control on a soften	NORMAL	3,995.01	0.30	39.28	3,953.12	112.03	458.30	471.42	1.84	-1.27	-149.37	-173.66
a care a reconstructive de exercicario de	NORMAL	4,090.01	0.48	118.74	4,048.12	112.03	458.81	471.91	0.54	0.19	83.64	114.21
per graduation of the considerant that the fo	NORMAL	4,185.01	0.88	125.29	4,143.11	111.42	459.75	472.72	0.43	0.42	6.89	14.28
SEC. 10. 10. 10. 10. 10. 10. 10. 10. 10. 10	NORMAL	4,279.01	1.11	149.51	4,237.10	110.22	460.80	473.51	0.50	0.24	25.77	73.80
na na in ann ann ann an an Ann Andrews	NORMAL	4,374.01	0.35	250.27	4,332.09	109,33	460.99	473.52	1.29	-0,80	106.06	163.69
e todana jama jama saratta	NORMAL	4,468.01	0.21	351.20	4,426.09	109.40	460.70	473.25	0.47	-0.15	107.37	152.12
2/20/2012	NORMAL	4,563.01	0.32	23.69	4,521.09	109.81	460.78	473.41	0.19	0.12	34.20	70.78
ART 1 (200) 21 (8) 1 (8) 1 (9) 1 (9) 1 (9)	NORMAL	4,657.01	0.24	54.72	4,615.09	110.17	461.04	473.74	0.18	-0.09	33.01	132.75
an attended attended to the second	NORMAL	4,752.01	0.32	92.13	4,710.09	110.27	461.47	474.18	0.21	0.08	39.38	85.83
arra area na arare neses	NORMAL	4,846.01	0.44	126.17	4,804.09	110.05	462.03	474.68	0.27	0.13	36,21	79,73
Transfer and the second second second second	NORMAL	4,941.01	0.56	150.87	4,899.09	109.43	462.55	475.06	0.26	0.13	26.00	73.62
rojeka yyökki oktobrajo kipis Asike	NORMAL	5,035.01	0.79	151.39	4,993.08	108.46	463.08	475.39	0.24	0.24	0.55	1.79
- Harry Joseph Table 170 Mill	NORMAL	5,130.01	0.97	135,66	5,088.07	107.31	463.96	476.02	0.32	0.19	-16,56	-61.35
and a second sec	NORMAL	5,224.01	0.44	0.92	5,182.06	107.10	464.52	476.53	1.40	-0.56	-143.34	-166.27
	NORMAL	5,319.01	0.18	355.22	5,277.06	107.62	464.51	476,63	0.28	-0.27	-6.00	-176.08

### 2.2.2 Survey Stations (Continued)

Date Ty	rpe	MD	Inc	Azi	TVD	N/S	E/W	V. Sec	DLeg	Build	Turn	TFace
		(ft)	o l	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)	(°)
2/20/2012 NORM/	٩L	5,414.01	0.09	333.59	5,372.06	107.83	464.47	476.63	0.11	-0.09	-22.77	-161.00
NORMA	AL :	5,508.01	0,18	162.20	5,466.06	107.76	464.48	476.62	0.29	0.10	-182.33	-174.26
NORM/	٩L	5,603.01	0.44	153.68	5,561.06	107.29	464.68	476.73	0.28	0.27	-8.97	-14.33
NORMA	<b>AL</b>	5,697.01	0.79	160.79	5,655.06	106.35	465.06	476.91	0.38	0.37	7.56	15.87
NORMA	٩L	5,792.01	0.70	239.81	5,750.05	105.44	464.77	476.45	1.00	-0.09	83.18	133.70
NORMA	٩L	5,887.01	0.74	228.77	5,845.04	104.75	463.81	475.37	0.15	0.04	-11.62	-79.48
NORMA	AL :	5,981.01	0.98	203.72	5,939.03	103.61	463.03	474.38	0.47	0.26	-26.65	-70.39
NORMA	AL	6,076.01	0.53	337.28	6,034.03	103.27	462.53	473.83	1.47	-0.47	140.59	164.06
NORMA	٩L	6,170.01	0.24	340.42	6,128.03	103.86	462,30	473.72	0.31	-0.31	3.34	177.41
NORMA	٩L	6,265.01	0.74	335.54	6,223.02	104.60	461.98	473.55	0.53	0.53	-5.14	-7.21
NORM/	<b>AL</b>	6,360.01	0.53	339.83	6,318.02	105.57	461.57	473.34	0.23	-0.22	4.52	169.38
NORMA	٩L	6,454.01	0.48	321.75	6,412.01	106.29	461.18	473.10	0,18	-0.05	-19.23	-116.32
NORMA	<b>AL</b>	6,549.01	0.38	309.54	6,507.01	106.80	460.69	472.72	0.14	-0.11	-12.85	-143.50
NORMA	٩L	6,643.01	0.90	336,55	6,601.01	107,68	460.16	472.37	0.62	0.55	28.73	44.10
NORMA	٩L	6,738.01	0.79	341,59	6,696.00	108.99	459.65	472.14	0.14	-0.12	5.31	148.46
NORMA	ΑL	6,832.01	0.53	25.62	6,789.99	109.99	459.63	472.32	0.59	-0.28	46.84	137.99
NORMA	ΑL	6,927,01	0.44	54.27	6,884.99	110.60	460.12	472.92	0.27	-0.09	30.16	124,29
NORMA	AL	7,022.01	0.62	131.63	6,979.98	110.47	460.80	473.56	0.71	0.19	81.43	116.70
NORMA	ΑL	7,116.01	0.84	133,94	7,073.98	109,66	461.68	474.26	0.24	0.23	2.46	8,78
NORM	AL	7,211.01	0.70	53.83	7,168.97	109,52	462.65	475.18	1.05	-0.15	-84.33	-136.22
2/21/2012 NORM	AL	7,305.01	0.93	354.42	7,262.96	110.61	463.04	475.78	0.89	0.24	-63.20	-105.81
NORM	AL	7,399.01	0.70	345.89	7,356.95	111,93	462.82	475.83	0.28	-0.24	-9.07	-156.41
NORMA	AL	7,494.02	0.26	34.58	7,451.95	112.67	462.80	475.96	0.59	-0.46	51.25	159.71
NORM	and the second section of the second	7,588.02	0.35	200,61	7,545.95	112,58	462.82	475.96	0.64	0.10	176,63	171.98
NORM	a a an an ar ar ar again.	7,683.02	0.67	183.41	7,640.95	111.75	462.69	475.66	0.37	0.34	-18.11	-34.34
NORM	AL	7,777.02	0.95	176.97	7,734.94	110.43	462.70	475.41	0.31	0.30	-6.85	-21.25
NORM	AL	7,872.02	1.10	170.64	7,829.92	108.74	462.89	475.26	0.20	0.16	-6.66	-40.24
NORM	AL	7,966.02	1.37	165.17	7,923.90	106.76	463.32	475.29	0.31	0.29	-5.82	-26.34
NORM	AL	8,061.02	1.05	203.93	8,018.88	104.87	463.26	474,86	0.90	-0.34	40.80	129.98
NORM	AL	8,155.02	1.32	216.08	8,112.86	103.21	462.27	473.56	0.39	0.29	12.93	49.12
NORM/	AL	8,250.02	1.52	211.44	8,207.83	101.25	460.97	471.89	0.24	0.21	-4.88	-32.23
NORM	a mercus services to a	8,345.02	2.20	192.87	8,302.78	98.39	459.91	470.29	0,95	0.72	-19.55	-51.08
NORM	canada e e e e e e e e e e e e e e e e e e	8,439.02	1.23	164.49	8,396.74	95.66	459.77	469.61	1.34	-1.03	-30.19	-152.39
2/22/2012 NORM/	erana area de este de la composición d	8,543.02	1.14	154.29	8,500.72	93,66	460.52	469.95	0.22	-0.09	-9.81	-118.15
NORM	and the area of the second	8,628.02	1.33	147.90	8,585.70	92.06	461.41	470.50	0.28	0.22	-7.52	-39.16
NORM	mananan indiri	8,723.02	1.41	144.53	8,680.67	90.17	462.68	471.37	0.12	0.08	-3,55	-46.90
NORM	and the second of the	8,817.02	1.31	154.69	8,774.65	88.26	463.81	472.10	0.28	-0.11	10.81	117.55
NORM/	and the second second	8,873.02	1.31	154.69	8,830.63	87.10	464.35	472.40	0.00	0.00	0.00	0.00